

ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर

निविदा सुचना सन 2025-2026

कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर हे मा. आमदार स्थानिक विकास कार्यक्रम अंतर्गत सन 2025-26 मधुन मौजे मुळेगांव तांडा (एकुण 4 ठिकाणी) तालुका दक्षिण सोलापूर गावामध्ये बोअरवेल, विद्युतपंप व पाण्याची टाकीसह पाणीपुरवठा सोय करणे हे काम करणे आहे. अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदारांकडून निविदा मागविण्यात येत आहेत. कोऱ्या निविदा विक्री दिनांक :- 03/12/2025 रोजी सकाळी 10.00 वाजले पासून दिनांक :- 10/12/2025 रोजी दुपारी 18.00 वाजे पर्यंत यांत्रिकी उपविभाग, जिल्हा परिषद, सोलापूर येथे (शासकीय सुट्टी दिवस वगळुन) उपलब्ध राहील.

निविदेचा तांत्रिक लिफाफा दिनांक शक्यतो :- 11/12/2025 रोजी उघडण्यात येईल.

अ. क्र.	कामाचे नांव	अंदाजपत्रकी य रक्कम रुपये	बयाणा रक्कम रुपये	निविदा शुल्क	कामपूर्ण करणेची मुदत	अधिकृत ठेकेदाराचा वर्ग
1	2	3	4	5	6	7
1	मौजे मुळेगांव तांडा तालुका दक्षिण सोलापूर, येथील एकुण 4 ठिकाणी येथे ग्रामपंचायत जागेत बोअरवेल, विद्युतपंप व पाण्याची टाकीसह पाणीपुरवठा सोय करणे.	3,99,244/-	4,000/-	100/-	90 दिवस	अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदार

- उपरोक्त सर्व कामाबाबत निविदा, अटी व शर्ती इत्यादी बाबतचा सर्व तपशिल निविदा संचामध्ये नमुद केलेला असून कोऱ्या निविदा संच उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर येथे मिळतील.
- उपरोक्त तक्त्यातील कामाचे नावासमोर रकाना क्रं. 04 मध्ये नमुद केलेल्या बयाणा रक्कम धनाकृष मुख्य लेखा वित्त अधिकारी, जिल्हा परिषद सोलापूर च्या नावे तयार करुन सदर निविदेतील तांत्रिक लिफाफा कागदपत्रासोबत देणे.
- निविदेच्या अटी शर्ती बदल करणे, प्राप्त निविदापैकी, एक किंवा सर्व निविदा कोणतेही कारण न देता नाकारणेचा हक्क निम्न स्वाक्षरीत यांनी राखुन ठेवला आहे.

उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर

कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

४

सविस्तर दरपत्रक सुचना

2025-26

1. सदर संपुर्ण निविदा प्रक्रिया निविदाद्वारे ऑफलाईन पद्धतीने आहे. सदर निविदेसंदर्भातील निविदा नोटीस प्रसिध्द, सुचना, शुध्दीपत्रके इत्यादीची माहिती www.zpsolapur.gov.in या संकेतस्थळावर उपलब्ध आहे.
2. निविदा सोबत खालील बाबी सादर करणे आवश्यक आहे.
(अ) सदर कामाची कोरी निविदा यांत्रिकी उपविभाग जिल्हा परिषद सोलापूर येथून रकाना क्र. 4 मध्ये नमुद रक्कमेचा राष्ट्रीयकृत बँकेचा धनाकर्ष / धनादेश जमा करण्यात यावे. संपुर्ण भरण्यात आलेले निविदा विहित वेळेत कार्यालयात जमा करावेत.
3. मक्तेदारांनी निविदा खालील प्रमाणे दोन लिफाफा (Two Envelope) मध्ये सादर करणे आवश्यक आहे.

(अ) तांत्रिक लिफाफा

1. निविदा फि रक्कम व निविदेची बयाना रक्कम जि.प.खाली भरणा केल्याच्या मुळ पावती (चलन)
2. फर्म नोंदणी प्रमाणपत्र.
3. **बोअरवेल, विद्युतपंपासह पाणीपुरवठा सोय करणे** दोन योजना पुर्ण केलेले कामाचा अनुभव दाखला जोडणे.
4. पॅनकार्डची स्कॅन केलेली प्रत.
5. जी.एस.टी. प्रमाणपत्राची स्कॅन केलेली प्रत.
6. निविदा नोटीस मधील सर्व अटी व शर्ती मान्य असल्याचे हमीपत्र तसेच निविदे सोबत सादर केलेली सर्व माहिती व कागदपत्र खरी असल्याचे व ती संपुर्ण प्रक्रियेच्या (निविदा सादर करणे ते पेमेंट अदा करणे व त्या नंतर) कोणत्याही वेळी खोटी अथवा चुकीची आढळल्यास त्यास संबंधित ठेकेदार / कंत्राटदार स्वतः जबाबदार व कार्यवाईस पात्र राहतील अश्या आशयाचे प्रतिज्ञापत्र 500 रुपये च्या स्टॅम्पवर देणे. (नोटरी / दंडाधिकारी यांचे समक्ष केलेले)

(ब) अर्थिक लिफाफा


- ❖ मक्तेदारांनी आपले दर विहीत ठिकाणी मध्ये योग्य त्या जागी भरून सदरची प्रत स्वतंत्र लिफाफा क्र. 2 मध्ये ठेवून लिफाफा बंद करावेत.
- ❖ लिफाफा क्र. 1 व लिफाफा क्र. 2 हे दोन्ही लिफाफा क्र. 3 मध्ये ठेवावेत.

दरपत्रकाच्या इतर अटी व शर्ती :

1. दरपत्रकाच्या किंमतीत अंदाजपत्रकानुसार साहित्य सर्व करांसहित पुरवठा करणे, उभारणी करणे, वाहतुक, पॅकींग व साहित्य गाडीत भरणे उत्तरविणे, कार्यान्वित करणे इत्यादी समावेश असेल.
2. निविदेतील सर्व साहित्य निविदेतील तांत्रिक निकषानुसार पुरवठा करावयाचे आहे. निविदेतील तांत्रिक निकषानुसार साहित्य नसल्यास ते स्विकारले जाणार नाही. सदरचे अधिकार उप अभियंता (यांत्रिकी) यांना असतील. सदर साहित्य नाकारले गेल्यास त्यांची जबाबदारी पुरवठाधारकाची राहिल.
3. पुरवठादाराचे सोलापूर जिल्ह्यामध्ये सेवा केंद्र (Service Center) असावे.
4. शासन निर्णय क्र. बीडीजी 2016 / प्र.क्र.2 / इमा 2 दिनांक :- 12/02/2016 अन्वये निविदा प्रक्रियेमध्ये प्राप्त निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा दहा टक्केयांपेक्षा अधिक दराने कमी असेल तर एवढ्या कमी दराने काम करण्याचे नियोजनाबाबत सविस्तर तपशिल सादर करण्यात यावा. तसेच निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्केयांपर्यंत कमी दराने असेल तर ठेकेदारांनी निविदाधिन किंमतीच्या 1 टक्के एवढ्या रक्कमेचा धनाकर्ष /

- धनादेश परफॉर्मन्स सिक्युरिटी म्हणुन निविदेच्या लिफाफा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्के पेक्षा जास्त दराने कमी असेल तर दराने 10 टक्के पेक्षा जेवढ्या दराने कमी आहे. तेवढ्या रक्कमेचा व वरीलप्रमाणे रक्कमेसह एकत्रित धनाकर्ष / धनादेश दराचा लिफाफा उघडल्यावर आठ दिवसात कार्यालयास सादर करणे. (उदा. 14 टक्के कमी दर 10 टक्क्यांपर्यंत 1 टक्का व व 14) - 10 टक्के) - 4 टक्के असे एकूण 5 टक्के)
5. आवश्यक कागदपत्रे / प्रमाणपत्रे सादर करण्यास तांत्रिक अडचणी असल्यास त्याबाबत निविदा स्विकारणे अथवा नाकारणे बाबत अंतिम निर्णय मा. कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर यांचा राहिल.
 6. निविदा / दरमंजूरी झाल्याचे कळविले नंतर निविदा प्रक्रियेतील कमीत कमी मंजूर दरानुसार कामे करण्यास / पुरवठा करण्यास तयार असल्याचे संमतीपत्र, रुपये 500/- किंमतीच्या स्टॅम्प पेपरवर साहित्य पुरवठा तथा अनुषंगीक कामे करण्यास तयार असल्याबाबत जिल्हास्तरावर करारनामा करून 7 दिवसाच्या आत द्यावा लागेल.
 7. सदर काम करताना कोणतीही हानी झाल्यास / अपघात झाल्यास त्याची सर्वस्वी जबाबदारी कंत्राटदाराची राहिल.
 8. अंदाजपत्रकातील साहित्याची तांत्रिक तपासणी उपअभियंता (यां), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर यांच्या कार्यालयाकडून करून घेतल्या शिवाय योजनेच्या स्थळी साहित्य आस्थापित करण्यात येऊ नये.
 9. अ) पुरवठा आदेश मिळाले पासून 2 महिन्याचे आत काम पूर्ण करणे आवश्यक आहे.
ब) जर कंत्राटदाराने विहित मुदतीत आदेशित काम पूर्ण केले नाही तर किंवा विलंबाचा संयुक्तीक खुलासा न केल्यास आदेशित कामाच्या पैकी बाकी असलेल्या कामाच्या किंमतीच्या अर्धा टक्का प्रति आठवडा या दराने दंड वसूल करण्यात येईल. हा दंड जास्तीत जास्त 5 टक्के रक्कम व अतिरिक्त सुरक्षा रक्कम जप्त करण्यात येईल. त्यानंतर सदरच्या मक्तेदारांचे नांव काळ्या यादीत समाविष्ट करण्यात येईल. पुन्हा फेर निविदा करून काम पूर्ण करण्यात येईल.
 10. देयकातुन सुरक्षा रक्कम, आयकर, जी.एस.टी. जिपसेस व इतर सर्व करांची शासकीय नियमानुसार वजावट करून देयक अदा करण्यात येईल.
 11. मक्तेदारांनी कामाचे नकाशे, निविदेतील अटी व शर्तीनुसार Specifications कामाचे स्थळ मंजूर व साहित्याची उपलब्धता या सर्व बाबींचा अभ्यास करून निविदा सादर कराव्यात.
 12. मक्तेदारांनी सादर केलेली निविदा व निविदेतील दर, लिफाफा क्रं. 2 उघडले नंतर 90 दिवसा पर्यंत वैध राहतील.
 13. निविदेतील सर्व वा कोणतीही अटी वा शर्ती पूर्ण न करणाऱ्या मक्तेदाराच्या निविदा व अर्धवट सादर केलेल्या निविदा अपात्र समजल्या जातील.
 14. कोणत्याही अटीवर (Conditional) आधारित दरपत्रके स्विकारल्या जाणार नाहीत अथवा स्विकारल्या तरी मंजूर केल्या जाणार नाहीत.
 15. निविदेच्या अटी व शर्ती मध्ये बदल करणे, प्राप्त निविदा पैकी एक किंवा सर्व निविदा कोणतेही कारण न देता रद्दचा हक्क निम्न स्वाक्षरीत यांनी राखून ठेवला आहे.
 16. संक्षिप्त निविदा सुचना व सविस्तर सुचना निविदा तंत्राचा एक भाग राहिल.
 17. कोणत्याही बाबीसाठी काही तंटा निर्माण झाल्यास त्याबाबत न्यायालयात जाता येणार नाही.


उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर


कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

DY ENGINEER (MECH)
MECHANICAL SUB DIVISION,
ZILLA PARISHAD, SOLAPUR
2025-2026

MLA FUND

ESTIMATE FOR

Village : - MULEGAON TANDA

Location : Word No. 2 Sathish Nagnath Pawar

Taluka : SOUTH SOLAPUR

Dist. SOLAPUR

**Name Of Work : Drilling Borewell And Providing , installing
ele.Pump, Water Tank And Distribution Pipe line Etc.**

ESTIMATED COST RS. 99,811.00

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.

Village : - MULEGAON TANDA

Taluka : SOUTH SOLAPUR

Location : Word No. 2 Sathish Nagnath Pawar

Dist : SOLAPUR

Name Of Work : Drilling Borewell And Providing , installing ele.Pump, Water Tank And Distribution Pipe line Etc.

ESTIMATE

PART NO. - A

Qty.	Item of work	Rate	Unit	Amount
1	2	3	4	5
	ITEM NO.1			
1.00	Bore Well Serve Charges	2500.00	Job	2500.00
	(GSDA rates)			
	ITEM NO.2			
60.00	Drilling For Borewell 115 mm	381.00	Job	22860.00
	(GSDA rates)			
	ITEM NO.3			
6.00	Providing , Fixing and grouting 140 mm PVC Casing Pipe 6Kg/cm with coulping at one end	704.00	Mtr	4224.00
	(GSDA rates 2020-21 dated 16.10.2020)			
	ITEM NO.4			
1	Borewell Yeild Testing Charges	1146.00	Job	1146.00
	(GSDA rates)			
		RS		30730.00
		Total RS		30730.00

PART NO. - B

Qty.	Item of work	Rate	Unit	Amount
1	2	3	4	5
	ITEM NO.1			
1.00	Supplying, erecting, testing and commissioning of minimum three & above star rated submersible pumpset of 1.125 kW/1.5 HP with 230 V, single phase, 50 Hz, A.C. supply suitable for 100 mm dia. borewell with 10 to 100 lpm discharge at 137 to 40 m head & discharge & delivery pipe of size-32 mm dia. with a necessary H type clamps as per specification no. WP-SMP. (DSR RATE 21255 + 5% = 22317.75)	22317.75	Job	22317.75
	(PWD ELE DSR 2022-23, Item No.12-2-38)			

1.00	ITEM NO.2 Supplying, erecting, testing and commissioning of D.O.L starter suitable for 250 V, single phase 50 Hz with overload element with necessary materials and connected to supply upto 3 HP. (DSR RATE 1166 + 5% = 1224.30)	1224.30	Job	1224.30
	(PWD ELE DSR 2022-23, Item No.12-4-1)			
4.00	ITEM NO.3 Providing & fixing Garware Wire rope 12 mm (Market R (Market Rate)	200.00	Kg	800.00
0.16	ITEM NO.4 Excavation for foundation / pipe trenches in hard murum including removing the excavated material upto a distance of 50 M and lifts as below, stacking and spreading as directed by Engineer-in-charge, normal dewatering, preparing the bed for foundation and excluding backfilling, etc. complete. (Bd-A-2/259)	187.00	Cum	29.92
	(MJP DSR 2023-24 ,Section E -I.No.2)			
0.16	ITEM NO.5 Providing and laying in situ Cement Concrete M-15 of trap/ granite / quartzite / gneiss metal for foundation and bedding including bailing out water, form work, compaction, curing, etc. complete. (Cement 5.90 bags / cum) b) In PCC M-150	5881.00	Cum	940.96
	(MJP DSR 2023-24 ,Section G - I.No. - 1(b)			
2.00	ITEM NO.6 PVC Aqua kraft type super bib tap 15 mm (PWD DSR 2022-23 (Building Bd-V) Sr.No.387)	240.00	No	480.00
6.00	ITEM NO.7 Providing and fixing on walls / ceiling / floor 25 mm dia. uPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete (PWD DSR 2022-2023, I.No.42.91 Sr.No.1462)	355.00	Rmt	2130.00
80.00	ITEM NO.8 Supplying and erecting high density polythene pipe ISI mark 32 mm dia. suitable for pressure of 6 kg/cm2 connected to jet / submersible pump with required material complete. (DSR RATE 57 + 5% = 59.85) (PWD ELE DSR 2022-23 I.No. 16-5-16)	59.85	Rmt	4788.00

ITEM NO.9			
0.075	Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates, etc. as per detailed design and drawing or as directed by Engineer - in - charge including cutting, fabricating, hoisting, erecting and fixing in position, making riveted bolted / welded connections and one coat of anticorrosive paint and over it two coats of oil painting, etc complete	114390.00	MT 8579.25
(MJP DSR 2023-24 ,Section F- I.No.6)			
ITEM NO.10			
500.00	Providing and fixing H.D.P.E. container Syntex or alike one piece moulded water tank made out of low density polythylene and built corrugation including of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow of all tanks capacity above 1000 to 20,000 litres	14.00	Rmt 7000.00
(PWD DSR 2022-23 , I.No.42.54 ,Sr.No.1425)			
ITEM NO.11			
85.00	Supplying and erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WG-MA/BW (DSR RATE 89 + 5% = 93.45)	93.45	mtr 7943.25
(PWD ELE. DSR 2023-24, Item no.1-3-3)			
ITEM NO.12			
1.00	M S Box For Starter (Market Rate)	1500.00	Sqm 1500.00
ITEM NO.13			
0.54	Material & labour for vinyl painting of matter given by dept. in diff. colour as per R.C (GSDA /SOLAR PUMP /RC /F- NO 25/834/2013-14 dt 1.3.2014)	1500.00	Sqm 810.00
TOTAL RS.			58543.43
Add GST 18 %			10537.82
TOTAL RS.			69081.25
TOTAL A + B			99811.25
R/O Rs.			99811.00

Prepared by


Jr. Engr./ Sect.Engr.
Mech. Sub-Division Z.P.
SOLAPUR


Deputy Engineer (Mech.)
Mech. Sub-Division Z.P.
SOLAPUR

Name Of Work : Drilling Borewell And Providing , installing ele.Pump, Water Tank And Distribution Pipe line Etc.

MEASUREMENT

ITEM NO.1

Supplying, erecting, testing and commissioning of minimum three & above star rated submersible pumpset of 1.125 kW/1.5 HP with 230 V, single phase, 50 Hz, A.C. supply suitable for 100 mm dia. borewell with 10 to 100 lpm discharge at 137 to 40 m head & discharge & delivery pipe of size-32 mm dia. with a necessary H type clamps as per specification no. WP-SMP.

= 1.00 Job

ITEM NO.2

Supplying, erecting, testing and commissioning of D.O.L starter suitable for 250 V, single phase 50 Hz with overload element with necessary materials and connected to supply upto 3 HP.

= 1.00 Job

ITEM NO.3

Providing & fixing Garware Wire rope 12 mm (Market Rate)

= 4.00 Kg

ITEM NO.4

Excavation for foundation / pipe trenches in hard murum including removing the excavated material upto a distance of 50 M and lifts as below, stacking and spreading as directed by Engineer-in-charge, normal dewatering, preparing the bed for foundation and excluding backfilling, etc. complete.

For Tank Steel Structures

M.		M.		M.		No.			
0.30	x	0.30	x	0.45	x	4.00	=	0.16	Cum
Total							=	0.16	Cum
Say							=	0.16	Cum

ITEM NO.5

Providing and laying in situ Cement Concrete M-15 of trap/ granite / quartzite / gneiss metal for foundation and bedding including bailing out water, form work, compaction, curing, etc. complete. (Cement 5.90 bags / cum)

a) For Tank Steel Structures

M.		M.		M.		No.			
0.30	x	0.30	x	0.45	x	4.00	=	0.16	Cum
Total							=	0.16	Cum
Say							=	0.16	Cum

ITEM NO.6

PVC Aqua kraft type super bib tap 15 mm

= 1.00 No.

ITEM NO.7

Providing and fixing on walls / ceiling / floor 25 mm dia. uPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete

= 5.00 Rmt

ITEM NO.8

Supplying and erecting high density polythene pipe ISI mark 32 mm dia. suitable for pressure of 6 kg/cm2 connected to jet / submersible pump with required material complete.

= 80.00 Rmt

ITEM NO.9

Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates, etc. as per detailed design and drawing or as directed by Engineer - in - charge including cutting, fabricating, hoisting, erecting and fixing in position, making riveted bolted / welded connections and one coat of anticorrosive paint and over it two coats of oil painting, etc. complete

1) Tank base Frame

Angle 50x50x6

Weight 4.50 kg/Mtr.

M.		No.		M.		Kg./M.		
1.00	x	4.00	=	4.00	x	4.50	=	18.00 Kg

2) Vertical legs

Angle 50x50x6

Weight 4.50 kg/Mtr.

M.		No.		M.		Kg./M.		
1.50	x	4.00	=	6.00	x	4.50	=	27.00 Kg

3) Supporting frame below tank base frame

Angle 40x40x6mm

Weight 3.50 kg/Mtr.

M.		No.		M.		Kg./M.		
1.00	x	4.00	=	4.00	x	3.50	=	14.00 Kg

4) Tank base sheet

M.S. Sheet 3.12 mm thick

Weight 16 kg/Sqm

M.		No.		M.		Kg./M.		
1.00	x	1.00	=	1.00	x	16.00	=	16.00 Kg

Total = 75.00 Kg

= 0.00 Kg

Total = 75.00 Kg

= 0.075 MT

Say = 0.075 MT

Add 5% Wastage

75.00 / 1000

ITEM NO.10

Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of low density polythylene and built corrugation including of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow of all tanks capacity above 1000 to 20,000 litres

= 500.00 Litrs.

ITEM NO.11

Providing and erecting mains with 2 core x 2.5 sqmm & earth wire 1.5 sqmm FR PVC copper wire in rigid PVC conduit minimum 20 mm Dia as per specification no.WG-MA/PC, para no.1.4.1

= 85.00 Rmt.

ITEM NO.12

M S Box For Starter

= 1.00 Nos

ITEM NO.13

Material & labour for vinyl painting of matter given by dept. in diff. colour as per R.C

= 0.54 SqM

Prepared by


Jr. Engr. / Sect. Engr.
Mech. Sub-Division Z.P.
SOLAPUR


Deputy Engineer (Mech.)
Mech. Sub-Division Z.P.
SOLAPUR

- वाचा :-1. जिल्हा परिषद व पंचायत समिती लेखा संहिता 1968 मधील नियम क्रं. 04 चे परिशिष्ट 2
 2. महाराष्ट्र शासन, शासन निर्णय क्रं. झेडपीए 2012 / प्र.क्र. 680 / वित्त - 09 / दिनांक :- 31 / 01 /2018.
 3. महाराष्ट्र शासन पाणी पुरवठा व स्वच्छता विभाग क्र. आपना/0222/प्र.क्र.292/पापु-15 दि. 30/09/2024.
 4. मा. जिल्हा नियोजन अधिकारी, सोलापूर यांचे कडील पत्र. क्रं. O/2025/May/ECL/00043 दि. 22/08/2025.

जा.क्र. उप अभियंता (यां)/याउवि/जिपसो/तांमा /E- 5876594(1) /2025

उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग,
 जिल्हा परिषद सोलापूर
 दिनांक :- 25 / 08 /2025

तांत्रिक मान्यता आदेश :-

उपरोक्त संदर्भीय क्रं. 01 चे अधिकार व संदर्भीय क्रं. 03 च्या शासन निर्णयान्वये शासनाचे प्रदान केलेल्या शक्तीचा उपयोग करून मी, उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग जिल्हा परिषद सोलापूर खालील प्रमाणे प्रस्तावित कामास तांत्रिक मान्यता प्रदान करत आहे.

अ.क्र.	गाव / तालुका / ठिकाण		कामाचे विवरण	योजना	संख्या	अंदाजपत्रीय खर्चाची रक्कम रुपये
	गाव	मुळेगांव तांडा	बोरवेल, विद्युतपंप व पाण्याची टाकीसह पाणी पुरवठा सोय करणे.	मा. आमदार स्थानिक विकास कार्यक्रम अंतर्गत सन 2025-26	1	99,811.00
	तालुका	दक्षिण सोलापूर				
	ठिकाण	वार्ड क्रं. 2 मध्ये सतिश नागनाथ पवार घराजवळ				
एकूण :-						99,811.00

अक्षरी :- नव्याणव हजार आठशे अकरा रुपये फक्त


 उप अभियंता (यांत्रिकी)
 यांत्रिकी उपविभाग
 जिल्हा परिषद सोलापूर

प्रति,

सरपंच / ग्रामसेवक

ग्रामपंचायत कार्यालय, मुळेगांव तांडा तालुका दक्षिण सोलापूर
 मा.गट विकास अधिकारी पंचायत समिती दक्षिण सोलापूर यांना माहिती व उचित कार्यवाहीस्तव.