

ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर

निविदा सुचना सन 2025-2026

कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर हे मा. आमदार स्थानिक विकास कार्यक्रम अंतर्गत सन 2025-26 मधुन मौजे नजिकर्षिपरी तालुका मोहोळ गावामध्ये जिल्हा परिषद शाळा येथे ग्रामपंचायत जागेत चिलर, शेड, आर.ओ. प्लॉन्ट बसविणे हे काम करणे आहे. अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदारांकडून निविदा मागविण्यात येत आहेत. कोऱ्या निविदा विक्री दिनांक :- 25 / 03 / 2026 रोजी सकाळी 10.00 वाजले पासून दिनांक :- 02 / 04 / 2026 रोजी दुपारी 18.00 वाजे पर्यंत यांत्रिकी उपविभाग, जिल्हा परिषद, सोलापूर येथे (शासकीय सुट्टी दिवस वगळुन) उपलब्ध राहिल.

निविदेचा तांत्रिक लिफाफा दिनांक शक्यतो :- 06 / 04 / 2026 रोजी उघडण्यात येईल.

अ. क्र.	कामाचे नांव	अंदाजपत्रकीय रक्कम रुपये	बयाणा रक्कम रुपये	निविदा शुल्क	कामपुर्ण करणेची मुदत	अधिकृत ठेकेदाराचा वर्ग
1	2	3	4	5	6	7
1	मौजे नजिकर्षिपरी तालुका मोहोळ, येथील जिल्हा परिषद शाळा येथे ग्रामपंचायत जागेत चिलर, शेड, आर.ओ. प्लॉन्ट बसविणे.	4,99,895/-	5,000/-	100/-	90 दिवस	अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदार

- उपरोक्त सर्व कामाबाबत निविदा, अटी व शर्ती इत्यादी बाबतचा सर्व तपशिल निविदा संचामध्ये नमुद केलेला असून कोऱ्या निविदा संच उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर येथे मिळतील.
- उपरोक्त तक्त्यातील कामाचे नावासमोर रकाना क्रं. 04 मध्ये नमुद केलेल्या बयाणा रक्कम धनाकृष मुख्य लेखा वित्त अधिकारी, जिल्हा परिषद सोलापूर च्या नांवे तयार करुन सदर निविदेतील तांत्रिक लिफाफा कागदपत्रासोबत देणे.
- निविदेच्या अटी शर्ती बदल करणे, प्राप्त निविदापैकी, एक किंवा सर्व निविदा कोणतेही कारण न देता नाकारणेचा हक्क निम्न स्वाक्षरीत यांनी राखुन ठेवला आहे.

उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर

कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

४

सविस्तर दरपत्रक सुचना

2025-26

1. सदर संपुर्ण निविदा प्रक्रिया निविदाद्वारे ऑफलाईन पध्दतीने आहे. सदर निविदेसंदर्भातील निविदा नोटीस प्रसिध्द, सुचना, शुध्दीपत्रके इत्यादीची माहिती www.zpsolapur.gov.in या संकेतस्थळावर उपलब्ध आहे.
2. निविदा सोबत खालील बाबी सादर करणे आवश्यक आहे.
(अ) सदर कामाची कोरी निविदा यांत्रिकी उपविभाग जिल्हा परिषद सोलापूर येथून रकाना क्र. 4 मध्ये नमुद रक्कमेचा राष्ट्रीयकृत बँकेचा धनाकर्ष / धनादेश जमा करण्यात यावे. संपुर्ण भरण्यात आलेले निविदा विहित वेळेत कार्यालयात जमा करावेत.
3. मक्तेदारांनी निविदा खालील प्रमाणे दोन लिफाफा (Two Envelope) मध्ये सादर करणे आवश्यक आहे.

(अ) तांत्रिक लिफाफा

1. निविदा फि रक्कम व निविदेची बयाना रक्कम जि.प.खाली भरणा केल्याच्या मुळ पावती (चलन)
2. फर्म नोंदणी प्रमाणपत्र.
3. **चिलर, शेड, आर.ओ. प्लॉन्ट बसविणे** दोन योजना पुर्ण केलेले कामाचा अनुभव दाखला जोडणे.
4. पॅनकार्डची स्कॅन केलेली प्रत.
5. जी.एस.टी. प्रमाणपत्राची स्कॅन केलेली प्रत.
6. निविदा नोटीस मधील सर्व अटी व शर्ती मान्य असल्याचे हमीपत्र तसेच निविदे सोबत सादर केलेली सर्व माहिती व कागदपत्र खरी असल्याचे व ती संपुर्ण प्रक्रियेच्या (निविदा सादर करणे ते पेमेंट अदा करणे व त्या नंतर) कोणत्याही वेळी खोटी अथवा चुकीची आढळल्यास त्यास संबंधित ठेकेदार / कंत्राटदार स्वतः जबाबदार व कार्यवाईस पात्र राहतील अश्या आशयाचे प्रतिज्ञापत्र 500 रुपये च्या स्टॅम्पवर देणे. (नोटरी / दंडाधिकारी यांचे समक्ष केलेले)

(ब) अर्थिक लिफाफा

- ❖ मक्तेदारांनी आपले दर विहित ठिकाणी मध्ये योग्य त्या जागी भरून सदरची प्रत स्वतंत्र लिफाफा क्र. 2 मध्ये ठेवून लिफाफा बंद करावेत.
- ❖ लिफाफा क्र. 1 व लिफाफा क्र. 2 हे दोन्ही लिफाफा क्र. 3 मध्ये ठेवावेत.

दरपत्रकाच्या इतर अटी व शर्ती :

1. दरपत्रकाच्या किंमतीत अंदाजपत्रकानुसार साहित्य सर्व करांसहित पुरवठा करणे, उभारणी करणे, वाहतुक, पॅकींग व साहित्य गाडीत भरणे उत्तरविणे, कार्यान्वित करणे इत्यादी समावेश असेल.
2. निविदेतील सर्व साहित्य निविदेतील तांत्रिक निकषानुसार पुरवठा करावयाचे आहे. निविदेतील तांत्रिक निकषानुसार साहित्य नसल्यास ते स्विकारले जाणार नाही. सदरचे अधिकार उप अभियंता (यांत्रिकी) यांना असतील. सदर साहित्य नाकारले गेल्यास त्यांची जबाबदारी पुरवठाधारकाची राहिल.
3. पुरवठादाराचे सोलापूर जिल्हायामध्ये सेवा केंद्र (Service Center) असावे.
4. शासन निर्णय क्र. बीडीजी 2016 / प्र.क्र.2 / इमा 2 दिनांक :- 12/02/2016 अन्वये निविदा प्रक्रियेमध्ये प्राप्त निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा दहा टक्केयांपेक्षा आधिक दराने कमी असेल तर एवढ्या कमी दराने काम करण्याचे नियोजनाबाबत सविस्तर तपशिल सादर करण्यात यावा. तसेच निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्केयांपर्यंत कमी दराचा असेल तर ठेकेदारांनी निविदाधिन किंमतीच्या 1 टक्के एवढ्या रक्कमेचा धनाकर्ष /

- धनादेश परफॉर्मन्स सिक््युरिटी म्हणुन निविदेच्या लिफाफा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्के पेक्षा जास्त दराने कमी असेल तर दराने 10 टक्के पेक्षा जेवढ्या दराने कमी आहे. तेवढ्या रक्कमेचा व वरीलप्रमाणे रक्कमेसह एकत्रित धनाकर्ष / धनादेश दराचा लिफाफा उघल्यावर आठ दिवसात कार्यालयास सादर करणे. (उदा. 14 टक्के कमी दर 10 टक्क्यांपर्यंत 1 टक्का व व 14) - 10 टक्के) - 4 टक्के असे एकूण 5 टक्के)
5. आवश्यक कागदपत्रे / प्रमाणपत्रे सादर करण्यास तांत्रिक अडचणी असल्यास त्याबाबत निविदा स्विकारणे अथवा नाकारणे बाबत अंतिम निर्णय मा. कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर यांचा राहिल.
 6. निविदा / दरमंजूरी झाल्याचे कळविले नंतर निविदा प्रक्रियेतील कमीत कमी मंजूर दरानुसार कामे करण्यास / पुरवठा करण्यास तयार असल्याचे संमतीपत्र, रुपये 500/- किंमतीच्या स्टॅम्प पेपरवर साहित्य पुरवठा तथा अनुषंगीक कामे करण्यास तयार असल्याबाबत जिल्हास्तरावर करारनामा करुन 7 दिवसाच्या आत दयावा लागेल.
 7. सदर काम करताना कोणतीही हानी झाल्यास / अपघात झाल्यास त्याची सर्वस्वी जबाबदारी कंत्राटदाराची राहिल.
 8. अंदाजपत्रकातील साहित्याची तांत्रिक तपासणी उपअभियंता (यां), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर यांच्या कार्यालयाकडून करुन घेतल्या शिवाय योजनेच्या स्थळी साहित्य आस्थापित करण्यात येऊ नये.
 9. अ) पुरवठा आदेश मिळाले पासुन 2 महिन्याचे आत काम पुर्ण करणे आवश्यक आहे.
ब) जर कंत्राटदाराने विहित मुदतीत आदेशित काम पुर्ण केले नाही तर किंवा विलंबाचा संयुक्तीक खुलासा न केल्यास आदेशीत कामाच्या पैकी बाकी असलेल्या कामाच्या किंमतीच्या अर्धा टक्का प्रति आठवडा या दराने दंड वसूल करण्यात येईल. हा दंड जास्तीत जास्त 5 टक्के रक्कम व अतिरिक्त सुरक्षा रक्कम जप्त करण्यात येईल. त्यानंतर सदरच्या मक्तेदारांचे नांव काढ्या यादीत समाविष्ट करण्यात येईल. पुन्हा फेर निविदा करुन काम पुर्ण करण्यात येईल.
 10. देयकातुन सुरक्षा रक्कम, आयकर, जी.एस.टी. जिपसेस व इतर सर्व करांची शासकीय नियमानुसार वजावट करुन देयक अदा करण्यात येईल.
 11. मक्तेदारांनी कामाचे नकाशे, निविदेतील अटी व शर्तीनुसार Specifications कामाचे स्थळ मंजूर व साहित्याची उपलब्धता या सर्व बाबीचा अभ्यास करुन निविदा सादर कराव्यात.
 12. मक्तेदारांनी सादर केलेली निविदा व निविदेतील दर, लिफाफा क्रं. 2 उघडले नंतर 90 दिवसा पर्यंत वैध राहतील.
 13. निविदेतील सर्व वा कोणतीही अटी वा शर्ती पुर्ण न करणाऱ्या मक्तेदाराच्या निविदा व अर्धवट सादर केलेल्या निविदा अपात्र समजल्या जातील.
 14. कोणत्याही अटीवर (Conditional) आधारित दरपत्रके स्विकारल्या जाणार नाहीत अथवा स्विकारल्या तरी मंजूर केल्या जाणार नाहीत.
 15. निविदेच्या अटी व शर्ती मध्ये बदल करणे, प्राप्त निविदा पैकी एक किंवा सर्व निविदा कोणतेही कारण न देता रद्दचा हक्क निम्न स्वाक्षरीत यांनी राखून ठेवला आहे.
 16. संक्षिप्त निविदा सुचना व सविस्तर सुचना निविदा तंत्राचा एक भाग राहिल.
 17. कोणत्याही बाबीसाठी काही तंटा निर्माण झाल्यास त्याबाबत न्यायालयात जाता येणार नाही.

उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर

कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

RURAL WATER SUPPLY DIVISION

ZILLA PARISHAD SOLAPUR

MECHANICAL SUB-DIVISION

ESTIMATE FOR

**NAME OF WORK : PROVIDING , SUPPLYING AND COMMISSIONING
OF REVERSE OSMOSIS SYSTEM 1000 LITRE PER HOUR WITH
Chiller And SHED**

VILLAGE NAME : NAJIK PIMPARI
LOCATION : Z.P.SCHOOL (G.P. AREA)
TALUKA : MOHOL
DIST : SOLAPUR

ESTIMATED COST RS. 499895.00

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Deputy Engineer (Mech) Sub.Division

NAME OF WORK : PROVIDING , SUPPLYING AND COMMISSIONING OF REVERSE OSMOSIS SYSTEM 1000 LITRE PER HOUR WITH
 Chiller And SHED

Village Name :- NAJIK PIMPAR

Taluka :- MOHOL

Dist : SOLAPUR

At :- Z.P.SCHOOL (Gram Panchayat Area)

ESTIMATE

Quantity	Unit	ITEM	Rate	Per	Amount
1	Set	ITEM NO.01 Providing, supplying and commissioning of 1000 LPH REVERSE OSMOSIS system with Drinking Water Automatic Dispensing Machine With One Years Warantity	256000.00	Set	256000.00
		The work contains following Items			
		1) Design			
		i) Flow Rate-1000 lit./hour			
		1.Raw Water Tank	1. Quantity	01 Nos	
			2. Moc	HDPE , IS:12701	
			3. Capacity	2000 Lit.	
			4. Accessories	Water Auto Censor	
		2.Raw Water Pump	1. Quantity	01 Nos.	
			2. Make	Kirloskar	
			3. Capacity	1 HP (0.75 KW)	
			4. Head	30 Mtr.	
			5. Discharge	2500 LPH	
			6. Accessories	Auto Cut Solenoid Valve	
		3. Pressure Sand Filter	1. Quantity	01 Nos	
			2. Vessel	F.R.P.	
			3. Vessel Size	13 X 54 Inch	
			4. Type	Down Flow	
			5. Type Of Media	Silica Sand Multi Grade	
			6. Accessories	Multi Port Valve	
			7. Make	Proton/Aster	
		4. Active Carbon Filter	2. Vessel	F.R.P	
			3. Vessel Size	13 X 54 Inch	
			4. Type	Down Flow	
			5. Type Of Media	Activated Carbon (900 IV)	
			6. Accessories	Multi Port Valve	
		5. Micron Cartridge Filter	1. Quantity	02 Nos(20 x 4inch dai.) (Big Jumbo) .	
			2. Cartridge	5 Micron	
			3. Capacity	0.5 Cum/Hour	
			4. Moc Of Cartridge	Polypropylene	
		6. Antiscalent Dosing System	1. Quantity	01 Nos.	
			2. Type	Electronic Dosing Pump	
			3. Dosing Capacity	6 LPH	
			4. Operating Pressure	2 Kg/sq.cm	
			5. Make	Proton/ E Dose.	
			6. Solution Tank	H.D.P.E.	
			7. Tank Capacity	100 Lit.	
		7. High Pressure Pump	1. Quantity	01 Nos.	
			2. Power	2 HP (1.5 Kw)	
			3. Capacity	1000 LPH	
			4. Flow	3000 LPH	
			5. Make	Crompton Greaves -Tera Flow/CRI/CNP /Leo/Lubi/ Shakti / Groundfos	
			6. Accessories	With Low Pressure Switch.	
		8. Chasis	1. Moc Of Chasis	S.S. Grid Chassis. Fully Machined	

9. Membranes	1. Quantity	04 Nos.
	2. Mack Of Vessel	Stainles Steel
	3. Type Of Membrane	Spirally Wounded
	4. Membrane	40-40 X 4 Nos.
	5. Housing	40 X 80 – 2 Nos.
	5. Capacity	1000 Lit/Hour
	6. Make	Adwyn Chemicals/DOW/ Hydrounotics
10. Instrumentation And Electrical Components	7. Accessories	Necessary size of Module And pressure Tube, Auto Flush with 3/4 Inches Solenoid Valve.
	1. Type	Fully Automatic
	2. Accessories	1. Pressure Gauge-2 Nos 2. Rotameter- 2400 – 1 Nos. 2400 – 1 Nos. 3. Electronic Control
11. Piping.	1. Raw Water Tank To Inlet	uPVC
	2. Out Let Of High Pressure	S.S.-304 Stainles Steel
12. UV Disinfection Unit	1. Quantity	01 Nos.
	2. Water Flow Rate	1000 LPH
	3. Type	Fluorescent Tube
	4. Make	ALFA/ Proton
13. Pure Water Storage Tank	1. Quantity	01 Nos
	2. Type	Vertical
	3. Capacity	2000 Lit.
	4. Moc Of Tank	Stainles Steel. Grade.
14. Dispense Unit (ATM)	1. Quantity	01 Nos.
	2. Type	Multi Coin (Rs.1 & 5)
	3. Moc of Dispense	Metal Body And Stainless Steel valves. With 50 Cards.
	4. Make	Aster / Proton /etc

(As Per Rates Sanctioned By E.E. RWS , Z.P.Solapur on 01.10.2020)

		Item No.2				
1	Nos	Chiller Of 2 Tonn Capacity , Chilling Range Minimum Water Temp 12C Discharge of Water 400 to 500 Ltrs/Hour (Compressor Make - Emerson / Kirloskar)	65000.00	Nos	65000.00	
(As Per Rates Sanctioned By E.E. RWS , Z.P.Solapur on 01.10.2020)						
1	Job	Shed for RO Plant	175421.69	Job	175421.69	
(As Per Rate Analysis)						
1	Job	Item No.3 Electrification And Wiring	2723.44	Job	2723.44	
(As Per Rate Analysis)						
0.5	SqM	Item No.4 Information board of scheme : Material & labour for painting of matter given by dept. in diff. colour as per R.C (0.9 X 0.6)	1500.00	SqM	750.00	
Rates Aprooved By GSDA /SOLAR PUMP /RC /F- NO 25/834/2013-14 dt 1.3.2014						
					TOTAL RS	499895.13
					SAY	499895.00

Estimate Prepared By


Jr. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur

Checked And Submitted By


Dy. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Rate Analysis For Providing & Erecting Reverse Osmosis System.

Items	Qty.	Rate	Per	Amt.
Item No. 1				
Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, flush type switch, earthing and required accessories as per specification No: WG-PW/SW	2.00	365.00	No	730.00
PWD Ele DSR 2022-23 Item No.1.7.17)				
Item No. 2				
Wiring for plug on board with Switch socket, copper wiring and earthing as per specification No: WG-PW/SW	2.00	116.00	No	232.00
PWD Ele DSR 2022-23 Item No.1.7.25)				
Item No. 3				
Supplying, erecting & marking DPMCB 6 A to 32 A B- series (for lighting) in provided distribution board as per specification no. SW- SWR/MCB	2.00	535.00	No	1070.00
PWD Ele DSR 2022-23 Item No.5.3.7)				
Item No. 4				
Supplying & erecting mains with 2x1.5 sq.mm. FRLSH copper wire, in 16gauge 20 mm dia. Rigid Steel conduit with continuous GI earth wire of 2.5 sq.mm. as per specification No: WG-MA/MC.	6.00	46.00	Mtr	276.00
PWD Ele DSR 2022-23 Item No.1.3.1)				
			TOTAL	2308.00
			GST 18%	415.44
			TOTAL Rs.	2723.44


Junior Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur


Dy. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Rate Analysis For Item No.2 Providing & Erecting Shed for 1000 LPH Reverse Osmosis System Shed.

Items	Qty.	Rate	Per	Amt.
ITEM NO.01 Excavation for foundation in earth soils of all types sand gravel and soft murum including removing the excavated material up to a distance of 50 M beyond the building area and stacking and spreading as directed as directed dewatering preparing the bed for foundation and necessary back filling ramming watering including shoring and strutting etc complete lift up to 1.50M(Mechanical Means)	2.59	239.00	Cum	619.49
(P.W.D.S.R. 22-23 Item No.12.02 (a))				
ITEM NO.02 Providing uncoursed rubble masonry of trap/granite/ quartzite /gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls/ in plinth of external walls including bailing out water manually, striking joints on unexposed faces and watering etc.complete.	4.32	5025.00	Cum	21708.00
PWD DSR 22-23 Item No.28.01				
ITEM NO.03 Filling in plinth and floors with approved excavated material in 15cm. To 20cm. Layers including watering and compacting etc. complete.	2.27	150.00	Cum	340.31
MJP DSR 2023-24 Item No.E-17				
ITEM NO.04 Providing and laying in situ cement concrete in M.10 of trap metal for foundation and bedding including bailing outwait formwork compacting and curing with natural sand etc complete.	1.20	5830.00	Cum	7005.84
(P.W.D D.S.R. 22-23 Item No.24.01				
ITEM NO.05 Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete.	0.26	119459.00	MT	30897.89
PWD DSR 22-23 Item No.23.01				
ITEM NO.06 Providing and fixing colour coated Zinalume (R) AZ150 (min 150 gms/sq.mt. total on each side) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness (BMT) (0.5 mm TCT), Hi-strength steel with min.550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND (R) steel quality super durable polyester paint coat (with inorganic pigment). The paint shall have a total coating thickness of nominal 35 um, comprising of nominal 25 um exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with subtle square fluting in the five pan at nominal 180-250 mm center- to-center. The end rib shall be designed for anti-capillary groove. and return leg. The feed materia' should have coil manufacturers product details marked a regular interval. Including fasteners with min. fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. complete. (weight of profile 4.52 Kilogram/ One Square Metre)	47.69	1173.00	Sq.M	55940.37
PWD DSR 22-23 Item No.38.05				
ITEM NO.07 Providing and fixing rolling shutter fabricated from steellaths of minimum thickness 0.9 mm with lockplate of 3.15mm thickness reinforced with 35x3x5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S.channel section of depth and thickness not less than 65mm and 3.15mm respectively with hold fast arrangements, M.S.Bracket plate 300x300x3.15mm minimum size and shape with square bar, suspensions haft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear weels and worms of high grade cast iron or mild steel and one coat of red lead primer etc.complete. (I.S. 62481979) (Without mechanical gear)	4.20	4829.00	Sq.M	20281.80
PWD DSR 22-23 Item No.39.24				
ITEM NO.08 Providing and laying Rough Shahabad Stone Flooring 25mm to 30mm thick and of required width In plain/ diamond pattern on a bed of 1:6 C.M. including cement float, striking joints, pointing In cement mortar 1:3 curing and cleaning etc. complete.	13.32	731.00	Sq.M	9738.75
(PWD DSR 2022-23 I.No.33.01)				
ITEM NO.09 Providing and fixing on walls / ceiling / floor 25 mm dia. uPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipeline if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	6.00	355.00	Mtr	2130.00
PWD DSR 2022-23, Item No.42.91				
			TOTAL	148662.45
			Add GST 18%	26759.24
			Gross Total	175421.69
			Say Rs.	175422


Junior Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur


Dy. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Name of Work-Rate Analysis For Item No.2 - Providing & Erecting Shed for 1000 LPH Water

Measurement sheet

Items	No	Length	Breadth	Depth	Qty.	Unit
ITEM NO.01						
Excavation for foundation in earth soils of all types sand gravel and soft murum including removing the excavated material up to a distance of 50 M beyond the building area and stacking and spreading as directed as directed dewatering preparing the bed for foundation and necessary back filling ramming watering including shoring and strutting etc complete lift up to 1.50M(Mechanical Means)						
For Wall	2.00	3.65	0.45	0.45	1.48	
For Wall	2.00	2.75	0.45	0.45	1.11	
			TOTAL		2.59	Cum
ITEM NO.02						
Providing uncoursed rubble masonry of trap/granite/ quartzite /gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls/ in plinth of external walls including bailing out water manually, striking joints on unexposed faces and watering etc.complete.						
For Wall	2.00	3.65	0.45	0.75	2.46	
For Wall	2.00	2.75	0.45	0.75	1.86	
			TOTAL		4.32	Cum
ITEM NO.03						
Filling in plinth and floors with approved excavated material in 15cm. To 20cm. Layers including watering and compacting etc. complete.						
	1.00	2.75	2.75	0.30	2.27	
			TOTAL		2.27	Cum
ITEM NO.04						
Providing and laying in situ cement concrete in M.10 of trap metal for foundation and bedding including bailing outwait formwork compacting and curing with natural sand etc complete.						
For Vertical square Pipe	5.00	0.30	0.30	0.45	0.20	
PCC Above Besment Flooring	1.00	3.65	3.65	0.08	1.00	
			TOTAL		1.20	Cum
ITEM NO.05						
Providing and fabricating structural steel work enrolled sections like joints channel s angles ,tees etc as per detailed design and drawings including fixing in position without connecting plates, braces,etc and one coat of anti corrosive paint and over it two coats of oil painting of approved quality and shade etc .						
M.S.Sq.Pipe 50x50x2.6mm	5.00	3.65	-	-	18.25	
Vertical Column Pipe	1.00	3.65	-	-	3.65	
Perling Pipe Top	5.00	3.65	-	-	18.25	
Wall harizantal Pipe (Wall No.1 to 3)	6.00	3.65	-	-	21.90	
Wall harizantal Pipe (Wall No.4)	1.00	1.50	-	-	1.50	
Wall harizantal Pipe (Wall No.4)				Total	63.55	RMT
		63.55	4.07	Kg/mtr	258.65	KG
		258.65	1000.00		0.26	MT
					0.00	
For Info Board				Total	0.26	
ITEM NO.06						

Items	No	Length	Breadth	Depth	Qty.	Unit
Providing and fixing plane zinc sheeting of 0.80 mm thick (22BWG) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt, galvanized iron screw and bolt and lead and bitumen washers complete(Wt 6.8kg/sqm)						
	2.00	3.65	-	2.90	21.17	
	2.00	3.65	-	2.90	21.17	
	1.00	3.65	3.65		13.32	
Deduction For Rolling Shutter	1.00		1.50	2.80	4.20	
Total					51.89	
Total Deduction					4.20	
					TOTAL	47.69 Cum
ITEM NO.07						
Providing and fixing rolling shutter fabricated from steellaths of minimum thickness 0.9 mm with lockplate of 3.15mm thickness reinforced with 35x3x5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S.channel section of depth and thickness not less than 65mm and 3.15mm respectively with hold fast arrangements, M.S.Bracket plate 300x300x3.15mm minimum size and shape with square bar, suspensions haft of minimum 32 mm diameter, hood cover of M.S.sheet not less than 0.9mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear weels and worms of high grade cast iron or mild steel and one coat of red lead primer etc.complete. (I.S. 62481979) (Without mechanical gear)	1.00		1.50	2.80	4.20	
ITEM NO.08						
Providing and laying Rough Shahabad Stone Flooring 25mm to 30mm thick and of required width in plain/ diamond pattern on a bed of 1:6 C.M. including cement float, striking joints, pointing in cement mortar 1:3 curing and cleaning etc. complete.	1.00		3.65	3.65	13.32	Sqm
ITEM NO.09						
Providing and fixing on walls / ceiling / floor 25 mm dia. uPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipeline if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.					8.00	mtr


 Junior Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur


 Dy. Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur

- वाचा :- 1. जिल्हा परिषद व पंचायत समिती लेखा संहिता 1968 मधील नियम क्रं. 04 चे परिशिष्ट 2
 2. महाराष्ट्र शासन, शासन निर्णय क्रं. झेडपीए 2012 / प्र.क्र. 680 / वित्त - 09 / दिनांक :- 31 / 01 / 2018.
 3. महाराष्ट्र शासन पाणी पुरवठा व स्वच्छता विभाग क्र. आपना/0222/प्र.क्र.292/पापु-15 दि. 30/09/2024.
 4. मा.जिल्हा नियोजन अधिकारी, सोलापूर यांचे अंदाजपत्रक मागणी पत्र क्रं. o/2025/Sep/ECL/00761 दि. 01/09/2025.

जा.क्र. उप अभियंता (यां)/याउवि/जिपसो/तांमा /E- 29/9/25 /2025

उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग,

जिल्हा परिषद सोलापूर

दिनांक :- 29/09/25

तांत्रिक मान्यता आदेश :-

उपरोक्त संदर्भीय क्रं. 01 चे अधिकार व संदर्भीय क्रं. 03 च्या शासन निर्णयान्वये शासनाचे प्रदान केलेल्या शक्तीचा उपयोग करून मी, उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग जिल्हा परिषद सोलापूर खालील प्रमाणे प्रस्तावित कामास तांत्रिक मान्यता प्रदान करत आहे.

अ.क्र.	गाव / तालुका / ठिकाण		कामाचे विवरण	योजना	संख्या	अंदाजपत्रीय खर्चाची रक्कम रुपये
	गाव	नजीकपिंपरी	चिलर शेड, आर.ओ. प्लॉन्ट बसविणे.	आमदार स्थानिक विकास कार्यक्रम अंतर्गत सन 2025-26	1	4,99,895.00
	तालुका	मोहोळ				
	ठिकाण	जि.प.शाळा येथे ग्रामपंचायत जागेत				
एकूण :-						4,99,895.00

अक्षरी :- चार लक्ष नव्याण्णव हजार आठशे पंच्याण्णव रुपये फक्त


 उप अभियंता (यांत्रिकी)
 यांत्रिकी उपविभाग
 जिल्हा परिषद सोलापूर

प्रति,

सरपंच / ग्रामसेवक

ग्रामपंचायत कार्यालय, नजीकपिंपरी तालुका मोहोळ
 मा.गट विकास अधिकारी पंचायत समिती मोहोळ यांना माहिती व उचित कार्यवाहीस्तव.