

कार्यालय गन्ना एवं चीनी आयुक्त उत्तराखण्ड काशीपुर (ऊधमसिंह नगर)।

website-www.sugarcane.uk.gov.in
Email.commissionercanesugar@gmail.com

निविदा सूचना

गन्ना एवं चीनी आयुक्त उत्तराखण्ड की ओर से मुख्यालय काशीपुर के परिसर में निम्नलिखित अनुरक्षण से सम्बन्धित कार्यों की मुहरबन्द निविदायें दिनांक 19/12/2025 को दिन के 1:00 बजे अपराह्न तक उपरोक्त कार्यालय में आमंत्रित की जाती है, जिन्हें उसी दिन अपराह्न 2:00 बजे उपस्थित ठेकेदारों/फर्म के समक्ष, कमेटी द्वारा खोला जायेगा।

क्रमांक	कार्य का नाम	कार्य की निविदा लागत (ला0रु0)	निविदा प्रपत्र का मूल्य (रु0में)	कार्य पूर्ण करने की अवधि	निविदा क्रय किये जाने हेतु अर्हता
1	गन्ना विकास एवं चीनी उद्योग के कार्यालय परिसर में साज-सज्जा एवं सेनीटरी कार्य।	15.90	1,500.00+ जी0एस0टी0	03 माह	गन्ना विकास एवं चीनी उद्योग विभागान्तर्गत भवन निर्माण कार्य में 'सी' श्रेणी अथवा इससे उच्चतर श्रेणी में पंजीकृत ठेकेदार
2	गन्ना विकास एवं चीनी उद्योग कार्यालय परिसर में स्थित चाहरदिवारी का उच्चीकरण का कार्य एवं अन्य अनुरक्षण कार्य।	20.79	2,000.00+ जी0एस0टी0	03 माह	गन्ना विकास एवं चीनी उद्योग विभागान्तर्गत विद्युत कार्य में 'ए' श्रेणी पंजीकृत ठेकेदार
3	गन्ना विकास एवं चीनी उद्योग कार्यालय परिसर में स्थित आवासीय/अनावासीय भवनों में आन्तरिक एवं बाह्य विद्युतीकरण का विस्तृत नवीनीकरण, सुदृढ़ अनुरक्षण कार्य।	24.98	2,000.00+ जी0एस0टी0	03 माह	गन्ना विकास एवं चीनी उद्योग विभागान्तर्गत भवन निर्माण कार्य में 'सी' श्रेणी अथवा इससे उच्चतर श्रेणी में पंजीकृत ठेकेदार
4	गन्ना विकास एवं चीनी उद्योग कार्यालय परिसर में स्थित चाहरदिवारी, नाली का मरम्मत एवं टाईप-1, 2 एवं 3 आवास के बाहरी दिवारों पेंट व अनुरक्षण कार्य।	17.97	1,500.00+ जी0एस0टी0	03 माह	गन्ना विकास एवं चीनी उद्योग विभागान्तर्गत भवन निर्माण कार्य में 'सी' श्रेणी अथवा इससे उच्चतर श्रेणी में पंजीकृत ठेकेदार
5	गन्ना विकास एवं चीनी उद्योग कार्यालय के आवासीय परिसर में स्थित टाईप-1, 2, 3, 4 एवं 4 (स्पेशल) आवास का अनुरक्षण एवं सेनीटरी का अनुरक्षण कार्य।	18.18	1,500.00+ जी0एस0टी0	03 माह	गन्ना विकास एवं चीनी उद्योग विभागान्तर्गत भवन निर्माण कार्य में 'सी' श्रेणी अथवा इससे उच्चतर श्रेणी में पंजीकृत ठेकेदार

निविदा दस्तावेज उपरोक्त कार्यालय से दिनांक 19/12/25 से दिनांक 23/12/25 तक कार्य दिवस में कय/उपरोक्त विभागीय वेबसाईट से डाउनलोड किये जा सकते हैं। निविदा प्रपत्र के साथ निविदा मूल्य व 2 प्रतिशत की धनराशि प्रस्तुत करनी होगी। निर्माण कार्य हेतु गठित कमेटी को एक अथवा समस्त निविदाओं को बिना कारण बताये निरस्त करने का अधिकार होगा। अन्य विवरण/शर्तें, निविदा प्रपत्र, बिल आफ क्वाटिन्टी व अनुबन्ध प्रपत्र में देखी जा सकती है।

(चन्द्र सिंह इमलाल)
अपर गन्ना एवं चीनी आयुक्त
उत्तराखण्ड, काशीपुर

कार्यालय गन्ना एवं चीनी आयुक्त उत्तराखण्ड काशीपुर

निविदा आमंत्रण प्रपत्र

(निविदादाताओं हेतु निर्देश, शर्तें एवं प्रतिबन्ध)

विज्ञप्ति सं०.....

उद्घोषणा/कार्य का नाम :

दिनांक, मूल्य रू०— 1500.00+जी०एस०टी०

गन्ना विकास एवं चीनी उद्योग के कार्यालय परिसर में साज-सज्जा एवं सेनीटरी कार्य।

1. मानक प्रपत्र :

विभागीय website- www.sugarcane.uk.gov.in पर निविदा दाताओं के उपयोगार्थ कार्य से संबंधित सामान्य निविदा, शर्तें निविदा प्रपत्र व मात्राकृत दर सूची शर्तों के साथ भी प्रदर्शित की जा रही है।

2. अनुमानित लागत रू०:

16.37 लाख

(कन्टीनजेंसी व G.S.T सहित)

2 अ. निविदा का प्रकार:

एकल प्रणाली

3. निविदा लागत (G.S.T सहित) रू० :

15.90 लाख

4. निविदा प्रतिभूति की धनराशि रू० :

रू० 32,000.00

4 A जमानत:

अनुबन्ध के पूर्व अनुबन्ध लागत का 10 प्रतिशत उत्तराखण्ड अधिप्राप्ति नियमावली 2025 के अधीन वाणिज्यिक बैंकों से निर्गत अदाता के नाम एकाउन्ट पेई डिमाण्ड ड्राफ्ट सावधि जमा रसीद या बैंक गारंटी आदि के रूप में अनिवार्यतः 5 प्रतिशत कार्यपूर्ति गारंटी एवं प्रतिपूर्ति निक्षेप हेतु 5 प्रतिशत को अलग अलग उपलब्ध करवाई जाएगी, जिसमें 5 प्रतिशत को Retention Money के रूप में प्रयोग किया जायेगा।

5. कार्य पूरा करने का समय :

3 माह

6. क्षतिपूर्ति प्रतिभूति

उत्तराखण्ड अधिप्राप्ति नियमावली 2025 के अधीन (निर्माण कार्य में विलम्ब के लिये संविदा मूल्य का 0.50 प्रतिशत प्रति सप्ताह परन्तु अधिकतम संविदा मूल्य का 10 प्रतिशत वसूला जायेगा)

7. निविदा की वैधता :

120 दिन

8. ठेकेदार का नाम :

.....

(जिसे निविदा फार्म बेचा गया तथा पूरा पता)

.....

9. ठेकेदार की वैध पंजीकृत श्रेणी :

.....

(स्वसत्यापित पंजीयन प्रमाण पत्र की छाया प्रति सहित)

10. निविदा फार्म के साथ कुल संलग्नको की संख्या :

.....

निविदा फार्म जारी करने वाले अधिकारी के हस्ताक्षर
सील

समान्य नियम व शर्तें:

1. निविदाओं का मुहरबन्द होना आवश्यक है अन्यथा किसी प्रकार की त्रुटि पाये जाने पर विभाग का कोई उत्तरदायित्व नहीं होगा।
2. निविदा खोलते समय सम्बन्धित ठेकेदार अथवा उसका प्रतिनिधि उपस्थित रह सकता है। निविदादाता की अनुपस्थिति में निविदायें खोलने के बाद किसी प्रकार की कोई आपत्ति मान्य नहीं होगी।
3. निविदा मुहरबन्द लिफाफे में संरक्षित कर प्रस्तुत की जाएगी। निविदादाता द्वारा लिफाफे के ऊपर अपर गन्ना एवं चीनी आयुक्त उत्तराखण्ड लिखा होना एवं विज्ञापन संख्या और कार्य का नाम उल्लेखित होना चाहिये।
4. कार्य के किसी भी आइटम की मात्राये घट/बढ़ सकती हैं जिसकी दर के सम्बन्ध में ठेकेदार का कोई क्लेम मान्य नहीं होगा। यदि किसी आइटम की यूनिट में मिसप्रिंट अथवा स्पेशिफिकेशन में अन्तर स्पष्ट होता है तो केन्द्रीय लोक निर्माण विभाग की शैड्यूल की यूनिट व अद्यतन विस्तृत स्पेशिफिकेशन मान्य होगी।
5. कार्य निर्धारित समय के अन्दर, समय सारणी के अनुसार पूर्ण करना होगा, अन्यथा ठेका रद्द कर तत्समय जमा जमानत की धनराशि (2 प्रतिशत अर्नेस्ट मनी को सम्मिलित कर) निक्षेपित/जब्त कर ली जायेगी। ठेकेदार द्वारा समय वृद्धि की माँग में दिये गये तर्कों को कनिष्ठ अभियंता, सहायक अभियन्ता व अधिशासी अभियन्ता की सहमति व शासन के तत्समय के नियमों के तहत ही समय वृद्धि दी जायेगी। इस विषय पर अनुबन्ध कर्ता अधिकारी का निर्णय स्वीकार होगा।
6. समस्त कार्य तथा उसका प्रत्येक आइटम विभागीय नियम निर्देश व स्पेशिफिकेशन के आधार पर सम्पन्न करना होगा। कार्य पूर्ण होने के 24 माह बाद तक कार्य में पायी जाने वाली त्रुटि के लिए ठेकेदार पूर्ण रूप से उत्तरदायी होंगे। इस अवधि में Retention Money विभाग में जमा रहेगी।
7. कार्य के अनुबन्ध के बीच यदि कोई विवाद उत्पन्न होता है तो अर्बिट्रेटर के रूप में गन्ना एवं चीनी आयुक्त उत्तराखण्ड का निर्णय अन्तिम व दोनों पक्षों को मान्य होगा।
8. यदि ठेकेदार के ऊपर विभाग की कोई धनराशि वाजिब रह जाती है तो उसकी वसूली कानूनी तौर पर राजस्व विभाग के माध्यम से की जायेगी।
9. कार्य की अन्तिम माप अंकित किये जाने तक समस्त मैटीरियल की देख-रेख व कार्य की स्टैविलिटी आदि का पूर्ण उत्तरदायित्व ठेकेदार का होगा।
10. एक अथवा समस्त निविदाओं को निरस्त करने का अधिकार अपर गन्ना एवं चीनी आयुक्त उत्तराखण्ड के पास सुरक्षित रहेगा।
11. तकनीकी निविदा के साथ 100/रु० मूल्य का नान ज्यूडीशियल नोटरीकृत शपथ पत्र प्रस्तुत करना होगा जिसमें निम्न बिन्दुओं का समावेश इस प्रकार आपेक्षित है कि:-
 - (1) पूर्व में उसकी पंजीकृत/फर्म को सम्पूर्ण राज्य उत्तराखण्ड व अन्य प्रदेश में किसी भी अधिप्राप्ति कर्ता संस्था द्वारा काली सूची में नहीं रखा गया है।
 - (2) निविदा दाता फर्म/ठेकेदार का निविदा कमेटी के किसी सदस्य से कोई सम्बन्ध नहीं है, कार्य प्रस्ताव अथवा सम्पादन के लिए नियामक की ओर से नियुक्त पदाधिकारी से कोई सम्बन्ध नहीं है।
 - (3) निविदा प्रपत्रों के साथ चाहे गये सभी प्रपत्र वैध रूप में प्रस्तुत किये गये हैं किसी तथ्य के असत्य, भ्रामक या असंवैधानिक पाये जाने पर निविदा निरस्त करने अथवा निविदा प्रतिभूति जब्त करने का अधिकार अपर गन्ना एवं चीनी आयुक्त उत्तराखण्ड काशीपुर में निहित होगा।
 - (4) शपथ पत्र में उद्घाटित तथ्य सत्य और साक्ष्यों के आधार पर सही है।
12. पावर आफ अटार्नी मान्य नहीं होगी।
13. निर्माण कार्य के दौरान किसी भी दुर्घटना व जानमाल के क्षति के लिये विभाग उत्तरदायी नहीं होगा।
14. स्वप्रमाणित जी०एस०टी० प्रमाण पत्र प्रस्तुत करना होगा।
15. ठेकेदार/फर्म को अध्यावधिक जी०एस०टी० का नापावना प्रमाण पत्र मूल रूप से लगाना अनिवार्य होगा।
16. सामग्री की मात्राओं के अनुसार सैम्पिल टेस्टिंग राज्य की प्रयोगशालाओं में कराया जायेगा जिसमें आने वाला व्यय ठेकेदार के बिलों से वसूला जायेगा। यदि ठेकेदार जानबूझ कर किसी सामग्री की क्वालिटी में विवाद पैदा करता है तो उसकी जाँच की फीस भी ठेकेदार के बिल से ही वसूली जायेगी।
17. कार्य की प्रगति के दौरान रनिंग भुगतान अनुबन्ध की धनराशि का 10 प्रतिशत से नीचे की धनराशि का नहीं किया जायेगा। माप पुस्तिका बनने के एक माह के अंदर भुगतान होगा। इस बीच की अवधि में ठेकेदार कार्य बंद नहीं करेगा।
18. निविदा विभागान्तर्गत पंजीकृत ठेकेदारों को ही बेची जायेगी।
19. ठेकेदार को यह ध्यान अवश्य रखना होगा कि गन्ना एवं चीन आयुक्त उत्तराखण्ड के मुख्यालय व आवासीय कालोनी की सुरक्षा व्यवस्था में आपके द्वारा कार्य कराये जाने के दौरान कोई कमी न होने पाये।

20. उत्तराखण्ड अधिप्राप्ति नियमावली 2025 के अनुसार न्यूनतम निविदा लागत के कार्य को ठेकेदार से जी0पी0डब्लू0 9 की शर्तों पर तैयार किये गये अनुबन्ध पर ठेकेदार को हस्ताक्षर करने होंगे। (अनुबन्ध प्रपत्र को कार्यालय में देखा जा सकता है)
21. उत्तराखण्ड अधिप्राप्ति नियमावली 2025 के अनुसार परफारमेन्स सिक्योरिटी डिपोजिट करनी होगी।
22. बिलो से नियमानुसार जी0एस0टी0, लेबर सेस, आयकर की कटौती की जायेगी। खनिज मेटैरियल में रायल्टी जमा करने का प्रमाण भी विभाग में उपलब्ध कराना होगा।
23. डाउनलोड निविदा प्रपत्र के मूल्य को निविदा पेट्री में निविदा डालने से एक दिन पूर्व की तिथि, के बैंक ड्राफ्ट (संयुक्त गन्ना एवं चीनी आयुक्त उत्तराखण्ड काशीपुर के पदनाम का बना हुआ) से अथवा विभाग में नगद जमा उपरान्त रसीद कटवाकर अदा करना होगा।
24. निविदादाता को विगत 03 वर्षों में निविदा लागत के मूल्य अथवा इससे अधिक लागत के कार्यों के संतोषजनक रूप से पूर्ण कराये जाने सम्बन्धी अनुभव प्रमाण पत्र निविदा प्रपत्र के साथ उपलब्ध कराया जाना अनिवार्य होगा।
25. निविदा धरोहर निविदा मूल्य का 2 प्रतिशत धन (टी0डी0आर0/एफ0डी0आर0/एन0एस0सी0 अपर गन्ना एवं चीनी आयुक्त उत्तराखण्ड के पदनाम का बना हुआ) के बिना कोई भी निविदा स्वीकार नहीं की जायेगी। मापदण्डों को पूरा करने वाले निविदा दाताओं की निविदा स्वीकार होने के एक सप्ताह के अन्दर सम्बन्धित ठेकेदार/फर्म को निविदा लागत का 10 (2 प्रतिशत प्रतिभूति सहित) प्रतिशत जमानत/कार्यपूर्ति प्रतिभूति/धरोहर की धनराशि एन0एस0सी0/एफ0डी0आर0 वाणिज्यिक बैंक से निर्गत अदाता के नाम एकाउण्ट पेई डिमाण्ड ड्राफ्ट/सावधि जमा रसीद या बैंक गारंटी के रूप में अपर गन्ना एवं चीनी आयुक्त उत्तराखण्ड काशीपुर के पदनाम से निर्गत हो (जिसमें से 5 प्रतिशत की धनराशि Defect liability अवधि तक के लिए वैध हो) प्रस्तुत करनी होगी तभी कार्यदेश दिया जायेगा।
26. निविदा स्वीकार किए जाने के बाद 7 दिन के अन्दर ठेकेदार को कार्यदेश प्राप्त करने हेतु प्रभावी कार्यवाही करनी होगी, अन्यथा 2 प्रतिशत प्रतिभूति की धनराशि जब्त कर निविदा निरस्त कर दी जायेगी।
27. शासनादेश संख्या 223817/2024/08(200)/XXVII(8)/2023 दिनांक 10.07.2024 के अनुसार जी0एस0टी0सम्बन्धी अदेय प्रमाण पत्र (No Due Certificate) निविदा कय करते समय प्रस्तुत करना अनिवार्य है।
28. निविदा प्रकाशन के उपरान्त विभाग में पंजीकृत नवीन ठेकेदार उक्त निविदा हेत मान्य नहीं होंगे।

मैं हम..... पुत्र श्री..... निवासी.....का हूँ/हैं। मैंने हमने उपरोक्त कार्य से संबंधित निविदा सूचना दिनांक..... को पढ़ी तथा कार्यस्थल, की पूर्ण जानकारी प्राप्त कर ली है। कार्यस्थल की समस्त परिस्थितियों, विभागीय नियम व शर्तों की दृष्टिगत रखते हुए मैं/हम अपनी निविदा प्रस्तुत कर रहा हूँ/कर रहे हैं तथा उपरोक्त कार्य को संलग्न बिल आफ क्वान्टिटी की दरों से..... (अंकों व शब्दों में) प्रतिशत कम/अधिक पर करने को तैयार हूँ/हैं।

जमा की गयी अर्नेस्ट मनी का विवरण निम्न प्रकार है—

रूपये.....

रसीद सं0.....दिनांक.....

बैंक ड्राफ्ट /एफ0डी0आर0 सं0.....

ह0 ठेकेदार

(कार्यालय कार्य के लिये)

आज दि0.....मे निविदा कमेटी द्वारा निविदा खोली गयी। निविदाये स्वीकृत/अस्वीकृत की गयी।

निविदा स्वीकृत करने वाले अधिकारी के हस्ताक्षर

निविदा कमेटी, के प्रस्ताव पर अपर आयुक्त/गन्ना एवं चीनी आयुक्त उत्तराखण्ड के प्रस्ताव सं0..... दिनांक.....द्वारा कार्य कराने की प्रशासनिक स्वीकृति प्रदान की गयी।

ह0 संयोजक

BILL OF QUANTITY

TENDER COST:- 15.90 लाख

Name Of Work :- गन्ना विकास एवं चीनी उद्योग के कार्यालय परिसर में साज - सज्जा एवं सेनीटरी का अनुरक्षण कार्य।

S.N	Dsr no	Description of Items	Qty.	Unit	Rate 2023 In rs	Amount in rs
A1		Civil work [visiting room]				
1	21.1.1.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	32.09	kg	495.05	15886.15
2.	15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	2.01	cum	2060.20	4141.00
3.	13.1.2	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	13.56	sqm	333.35	4520.23
4.	6.4.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	1.50	cum	9105.95	13749.98
5.	5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	43.88	sqm	927.25	40687.73
6.	5.33.2.1	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge.	6.98	cum	9860.40	68825.59

Rajesh
J.E

[Signature]
A.E

[Signature]
E.E.

		(Note :- Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/recoverable separately). All works above plinth level upto floor V level				
7.	5.22A.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	685.78	Kg	107.85	73961.37
8.	26.23.1	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), umidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal powder coated T-Grid of hot dipped galvanised iron section of 0.40 mm thick on Silhouette profile, rotary stitched double webbed white with 6mm reveal profile (white/black), comprising of main-T runners of size 15x42mm of length 3000 mm, cross - T of size 15x42 mm of length 1200 mm and secondary intermediate crossT of size 15x42 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger Unit Rate No. 428 SUB HEAD : 26.0 NEW TECHNOLOGIES AND MATERIALS rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 22x19x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick integral densified micro edge light weight calcium silicate false ceiling tiles	35.70	sqm	2630.40	93905.28
9.	13.81.1	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and manufacturer including applying additional coats wherever required to achieve even shade and colour Old work (one or more coats)	38.50	sqm	62.70	2413.95
10.	9.100.1	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC-10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 125 mm	4	each	66.25	265.00
11.	21.4.1	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineerin-chargeWith stainless steel cover plate minimum 1.25 mm thickness	2	each	2823.85	5647.70
12.	15.41	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	35.70	sqm	56.35	2011.70

for 184
J/B

AE

E.E.

13.	21.3.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item With float glass panes of 8 mm thickness (weight not less than 20 kg/sqm)	12.57	sqm	1685.40	21185.48
14.	21.7.2	Providing and fixing machine moulded aluminium covering of approved pattern & design, made out of machine cut aluminium sheet and machine holed for receiving dash fastener, over expansion joints on vertical surfaces/ceiling floors, the fixing on plate in one row on one side of joint only shall be done with stainless steel dash fasteners of 8 mm dia and 75 mm long bolt including providing aluminium washers 2 mm thick & 15 mm dia, at a staggered pitch of 200 mm centre to centre including drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. complete as per direction of Engineer-in-charge. Powder coated aluminium sheet 2.5 mm thick (minimum thickness of powder coating 50 micron)	47.42	kg	716.40	33971.69
15.	9.97.1	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :300x10 mm	2	Each	130.10	260.20
16.	9.96.1	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm	2	Each	303.25	606.50
17.	9.101.2	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	1	Each	72.35	72.35
		Total A1 civil work [visiting room]				382111.90
A2		CIVIL WORK [office]				
1.	15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm.to 25 mm.	122.50	M2	73.4	8991.50
2.	11.41A.2.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete glazed vitrified floor tiles polished finish of size 600x1200 mm	159.74	M2	1798.80	287340.31
3.	11.48.2	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge. Size of Tile 600x600 mm	159.74	M2	309.05	49367.64

Rajesh
J.E

G. J. E

E.E

4.	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm(thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	57.73	M2	1096.55	63303.83
5.	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	14.21	M2	1267.95	18017.56
6.	m/r m/p	Providing and fixing in position PVC paneling of 10 mm thick in approved colour, the panels shall have profiled interlocking system locked in place with pins (ditty) all complete as per direction of the engineer in - charge. (area of portion out side beading or rebates to be measured).	88.28	M2	1908.00	168438.24
7.	m/r m/p	Supply and fixing blinder with necessary accessories including all complete as per direction of the engineer in - charge.	19.57	M2	3000.00	58710.00
		Total A2 civil work				654169.08
B		Sanitary work				
1.	m/r m/p	Dismantling of all sanitary pots including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	1	job	10000.00	10000.00
2.	15.44.1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : 15 mm to 40 mm nominal bore	50.00	Rmt	149.80	7490.00
3.	18.10.1	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore	18.00	Rmt	366.40	6595.20
4.	18.10.2	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 20 mm dia nominal bore	18.00	Rmt	437.30	7871.40
5.	18.10.4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 32 mm dia nominal bore	18.00	Mtr	667.00	12006.00
6.	17.3.1	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	10	Each	8006.60	80066.00

Signature
J.L.B

Signature
AE

Signature
E.E.

7.	17.1.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) : Orissa pattern W.C. pan of size 580x440 mm	2	No	6767.40	13534.80
8.	18.51.1	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore each.	22	Each	798.95	17576.90
9.	17.18.1	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fitting and fixtures complete. 10 litre capacity - White	2	No	1190.65	2381.30
10.	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	4000.00	Ltr	11.00	44000.00
11.	18.21.1	Providing and fixing unplasticized PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore	33	no	85.00	2805.00
12.	18.53.1	Providing and fixing C.P. brass angle valve for basin mixer and geoints of approved quality conforming to IS:8931 15mm nominal bore	45	No	574.30	25843.50
13.	18.58.1	Providing and fixing PTMT grating of approved quality and colour. Circular type 100 mm nominal dia	29	No	37.60	1090.40
14.	18.62.1	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminums rod with L.P./ H.P.H.D. plastic ball. 15 mm nominal bore, 105 mm long, weighing not less than 138 gms	4	No	182.10	728.40
15.	17.7.11	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: Stainless Steel AISI-304(18/8) Wash basin 530x345 mm with single 15 mm C.P. brass pillar tap	14	Each	4149.75	58096.50
16.	17.8	Providing and fixing white vitreous China pedestal for wash basin completely recessed at the back for the reception of pipes and fittings	15	Each	1683.35	25250.25
17.	18.65	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	14	No	111.45	1560.30
18.	17.16A	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube up to 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - In - charge.	10	Each	349.15	3491.50
19.	17.34.1	Providing and fixing toilet paper holder : C.P. brass	10	Each	803.70	8037.00
20.	17.22B	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer in charge. (a) 15 mm nominal dia	10	Each	6940.75	69407.50

Rajesh
J E

olep
A E

E.E.

21.	17.28.2.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete, 32 mm dia	14	Each	119.55	1673.70
22.	17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	4	Each	1607.95	6431.80
23.	17.32.2	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic molded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 453x357 mm.	3	Each	1361.80	4085.40
24.	17.4.3	Providing and fixing white vitreous China flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Range of three urinal basins with 10litre white P.V.C. automatic flushing cistern	3	Each	13417.30	40251.90
25.	17.73.2	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	8	Each	708.95	5671.60
26.	18.22.1	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 18.22.1 100 mm diameter	2	Each	193.95	387.90
27.	m/r	Providing and fixing C.P. brass mixture cock of approved quality conforming to IS standards and weighing not less than 1000 gms. 15 mm nominal bore each.	5	Each	1000.00	5000.00
28.	18.56.2	Providing and fixing PTMT pillar cock of approved quality and colour. 15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gms	1	Each	224.10	224.10
29.	18.12.2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 20 mm dia nominal bore	12.00	Metre	368.60	4,423.20
30.	17.7.3	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps	1	Each	2301.75	2301.75
		Total sanitary work				468283.30
c		Electrification work				
1.	1.10.2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	15	Point	1182.00	17730.00
2.	1.12	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	90.00	Mtr	334.00	30060.00

Rajesh
J.E

Alal
A.E

Raj
E.E

3.	1.24.1	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 5/6 A switch	10	Each	103.00	1030.00
4.	1.24.8	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. For Bell push	1	Each	140.00	140.00
5.	1.25	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2	Each	369.00	738.00
6.	1.26	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	2	Each	40.00	80.00
7.	1.32	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	2	Each	586.00	1172.00
8.	1.38	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	1	Each	99.00	99.00
9.	1.45	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet cover on the fan box etc. as required.	2	Each	339.00	678.00
10.	1.50.1	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. 1.50.1 Up to 450 mm sweep.	2	Each	450.00	900.00
11.	2.10.1	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	2	Each	256.00	512.00
12.	2.11	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	2	Each	13.00	26.00
13.	2.14.1	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 25 A	2	Each	2028.00	4056.00
14.	1413 CATT AA	Supplying and fixing Wall bracket LED Tube light with batten suitable for up to 1x22 LED Tube light fitting tube on surface complete in all respect fixture havells.	4	Each	1203.60	4814.40
15.	m/r	Supply of 1200 mm swip ceiling fan.	2	Each	2000.00	4000.00
16.	m/r	Supplying and fixing ceiling light (600x600) mm in false ceiling.	6	Each	3000.00	18000.00
17.	m/r	Wall bracket (wash room) 9w LED light fixture havells.	1	Each	1000.00	1000.00
		total electrical work				85035.40
		Total work [A1 + A2 + B + C]				158959.68

Say 15,89,596.88

Signature
J E


Signature
A E


Signature

शर्तें:-

1. अनुबन्ध स्टाम्प ड्यूटी नियमानुसार जमा करनी होगी।
2. आगणित निविदा लागत अंको व शब्दों में भरी जायेगी। निविदा प्रपत्र में कोई भी मॉगी गयी सूचना खाली नहीं रखी जाएगी।
3. बढ़ी हुई मात्राओं का स्वीकृत निविदा दर पर भुगतान किया जायेगा।
4. यदि बिल आफ क्वांटिटी से इतर आइटमों पर कार्य ठेकेदारों से कराया जाता है तो वर्तमान शैड्यूल आफ रेट्स पर इनका भुगतान सक्षम प्राधिकारी की स्वीकृति उपरान्त किया जायेगा।
5. निविदा डालने से पूर्व ठेकेदार प्रस्तावित कार्य का ले आउट, ड्राईंग व कार्य स्थल का निरीक्षण भली प्रकार कर लेवे।
6. अन्तिम बिल भुगतान की कार्यवाही गुणवत्ता की संतोषजनक रिपोर्ट के पश्चात की जायेगी।
7. यदि अपरिहार्य कारणों से निविदा प्रपत्र/खोलने के दिवस को राजकीय अवकाश घोषित हो जाता है तो अगले कार्य दिवस को कार्यवाही सम्पादित की जायेगी। यदि किसी निविदा दाता को निविदा बेच दी जाती है तो इसका यह अर्थ नहीं लगाया जा सकेगा कि वह निविदा देने हेतु पात्र है।
8. कार्य में प्रयुक्त होने वाली समस्त सामग्री की व्यवस्था निविदा दाता को स्वयं करनी होगी तथा स्थल पर सामग्री की सुरक्षा की जिम्मेदारी ठेकेदार की होगी।
9. निविदा प्रपत्र केवल विज्ञापन में उल्लिखित वांछित श्रेणी में पंजीकृत ठेकेदारों को ही मूल पंजीकरण प्रमाण दिखाने पर विक्रय किये जायेंगे।
10. निविदा में भरे गये तथ्यों के सम्बन्ध में प्रमाणित पत्रों की छाया प्रतियाँ लगानी अनिवार्य है।
11. कार्य स्थल पर घटित किसी भी प्राकृतिक तथा मानवीय आपदा के लिए विभाग जिम्मेदार नहीं होगा, समस्त जिम्मेदारी संबंधित ठेकेदार की होगी। कार्य के लिए Defect liability period दो वर्ष होगा। उक्त बिल ऑफ क्वांटिटी की स्पेसिफिकेशन अस्पष्ट होने की दशा में C.P.W.D Circle Delhi की स्पेसिफिकेशन अन्तिम रूप से मान्य होगी।
12. बिल आफ क्वांटिटी में उल्लेखित आइटम के पूर्ण होने पर ही उस आइटम को अन्तिम बिल में सम्मिलित किया जायेगा।
13. कार्य से संबंधित मजदूरों की कार्य स्थल में कार्य के समय यदि कोई दुर्घटना होती है तो इसके लिये विभाग उत्तरदायी नहीं होगा।
14. कार्य के दौरान किसी भी प्रकार का विवाद होने पर गन्ना एवं चीनी आयुक्त उत्तराखण्ड का निर्णय अन्तिम एवं मान्य होगा।
15. विभाग की बिजली एवं पानी के उपयोग करने पर वाजिब बिल की कटौती बिल से की जायेगी।
16. अधूरे आइटम के आधार पर उस मद में कोई भुगतान नहीं किया जायेगा।
17. कार्यदेश धन की उपलब्धता एवं कार्य की प्राथमिकता के आधार पर दिया जायेगा।
18. शर्तें निविदा मान्य नहीं होगी।
19. प्रस्तावित कार्य की स्पेसिफिकेशन अनुसार स्थल पर कार्य, कनिष्ठ अभियन्ता की देख-रेख में किया जायेगा।
20. कार्य निर्धारित समय के अन्दर पूर्ण न करने पर अथवा गुणवत्ता-युक्त कार्य न पाये जाने की दशा में जी0पी0डब्लू0-9 की शर्तों के अनुसार कार्यवाही की जायेगी।
21. सभी प्रकार के टैक्स की कटौती बिल भुगतान के समय लागू नियमों के अनुसार होगी।
22. कार्य का भुगतान मापन के आधार पर किया जायेगा।
23. यदि किसी स्पेसिफिकेशन में अस्पष्टता प्रतीत होती है तो C.P.W.D का C.P.W.D Standard bidding document मान्य होगी।
24. अनुरक्षण का कार्य कार्यालय एवं आवासीय परिसर में निवासित कार्मिकों के आवासों में होना है इसलिये निविदादाता यह सुनिश्चित कर ले कि अनुरक्षण कार्य के दौरान कार्यालय कार्य में कोई व्यवधान तथा आवासीय कालोनी में निवासित कार्मिकों को कोई असुविधा उत्पन्न हो।
25. शासनादेश संख्या 223817/2024/08(200)/XXVII(8)/2023 दिनांक 10.07.2024 के अनुसार जी0एस0टी0सम्बन्धी अदेय प्रमाण पत्र (No Due Certificate) निविदा कय करते समय प्रस्तुत करना अनिवार्य है।
26. निविदा प्रकाशन के उपरान्त विभाग में पंजीकृत नवीन ठेकेदार उक्त निविदा हेतु मान्य नहीं होंगे।

प्रस्तावित कार्य को निर्धारित समय अन्तर्गत पूर्ण कराते हुए विभिन्न वस्तुओं/कार्यों/घटकों का रंगीन फोटो (जो कि अध्यावधिक किये गये कार्य की प्रगति दर्शाता हो) कार्यालय में जमा करने के साथ किये गये कार्य का बिल प्रस्तुत करना होगा।


कनिष्ठ अभियन्ता
मुख्यालय काशीपुर


सहायक अभियन्ता
ऊधमसिंहनगर


अधिशाली अभियन्ता
उत्तराखण्ड

बिल ऑफ क्वांटिटी में दी गई दस शर्तें एवं टेण्डर शर्तों को मैंने भली भाँति पढ़ लिया है। इन्हीं के आधार पर निविदा प्रपत्र में अपनी निविदा दर भरकर इसे निविदा फार्म के साथ संलग्न कर बन्द लिफाफे के अन्दर रखते हुये निविदा पेटी में डाल रहा हूँ

हस्ताक्षर ठेकेदार