


सिलवासा नगर पालिका SILVASSA MUNICIPAL COUNCIL





इ-मेल/E-mail: silvassamunicipalcouncil@gmail.com Phone No.: 0260-2633193, Mobile No.: +91 8347472611

Website: smcdnh.in

No. SMC/CO/ENGG/SEW/2025/208/5970

Date:-29/09/2025

Subject: - "Laying Sewerage Pipe line from SPS-7 to Ring Road Crossing near Ekdant Square in SMC Area".

-: LIMITED TENDER NOTICE NO. 07 OF 2025-26 : -

On behalf of the President of India, the Chief Officer, Silvassa Municipal Council, Dadra & Nagar Haveli, Silvassa has invites sealed limited tender/bid from interested Agencies/Contractors/firms for the work of "Laying Sewerage Pipe line from SPS-7 to Ring Road Crossing near Ekdant Square in SMC Area" so as to reach to undersigned on or before 06/10/2025 up to 13.00 hours by post/courier or by hand delivery.

Sr. No.	Description of item	Qty.	Unit	Rate (in Rs.)	Amount (Including GST)
1.	Providing and Supplying D.I. K-9 grade pipes for following nominal bore diameter with internal cement mortar lining including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading conveyance to Department stores, stacking etc. complete. (IS 8329-2000). Rate for DI pipe based on wholesale price index of Pig iron as 157.6 for the month of dec -2022. For Sewerage project cement mortar lining shall be with sulphate resistance cement. 250mm	70.00	Rmt.		
2.	Manufacture, Supply & Delivery of ductile iron, flanged socket, spiggot bands, tees, bends, reducres or any other specials as per BS-EN-545/1995 Class-A series K12 suitable for use with D.I Pipes manufactured as per IS: 8329/1994 delivery of specials is to be made to GWSSB store or site of works anywhere in Gujarat incl. all taxes, loading, unloading, carting, stacking, insurance, inspection charges, octroi etc. complete. With external Bitumin and Zinc coating and internal cement mortar lining. 80 to 300 mm dia	500.00	Kg.		
3.	Providing and supplying C.I Temper proof Air-valves with S. S with 304 float gun metal, nozel of approved make and quality of following class and diameter including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance to departmental stores, stacking etc. complete.	1.00	No.		

	Temper Proof Air Valve (Without Isolating Sluice Valve PN 1.6)			
4.	50 mm Excavation for pipe line trenches incl all safety provisions using site rails &	59.40	Cum.	
	stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as			
	specified. Upto 1.50 mt Depth In all sorts of soil and Soft murrum			
5.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. Upto 1.50 mt Depth In hard murrum, boulders incl. Macadam road	89.10	Cum.	
6.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. Upto 1.50 mt Depth In hard rock and / or in C.C 1:2:4 or RCC blasting, breaking, chiseling, or buy chiseling or breaking only	74.25	Cum.	
7.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 1.50 mt to 3.00 mt Depth In soft rock and / or masonary in Cm or LM/Line concrete (50%)	37.13	Cum.	
8.	Excavation for pipe line trenches incl all safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 1.50 mt to 3.00 mt Depth In hard rock and / or in C.C 1:2:4 or RCC blasting, breaking, chiseling, or buy chiseling or breaking only (50%)	37.13	Cum.	
9.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 3.00 mt to 4.50 mt Depth In soft rock and / or masonary in Cm or LM/Line concrete (50%)	18.56	Cum.	

		40 -	· ~ '	
11.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 3.00 mt to 4.50 mt Depth In hard rock and / or in C.C 1:2:4 or RCC blasting, breaking, chiseling, or buy chiseling or breaking only (50%) Excavation for pipe line trenches inclall safety provisions using site rails &	9.28	Cum.	
	stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 4.50 mt to 6.00 mt Depth In soft rock and / or masonary in Cm or LM/Line concrete (50%)			
12.	Excavation for pipe line trenches inclall safety provisions using site rails & stacking excavated stuff up to a lead of 90 mt clearing the site etc. complete for lifts and strata as specified. 4.50 mt to 6.00 mt Depth In hard rock and / or in C.C 1:2:4 or RCC blasting, breaking, chiseling, or buy chiseling or breaking only (50%)	9.28	Cum.	
13.	Excavation in bitumen Road as per required gradient and line including safety provisons using site rails and stacking excavated stuff including up to all required lead cleaning the site etc.,	31.50	Cum.	
14.	Dewatering in all sorts soil and soft murrum and boulders, soft rock ,hard rock, upto 1.5mt, depth from G.L	94.50	Cum.	
15.	Providing bedding incl. raing, watering, levelling, consolidating etc. Complete as per standard and instruction of engineer incharge	9.45	Cum.	
16.	Lowering, laying and jointing DI pipes and specials of following class and diameter (By butt fusion welding method) including cost of conveyance from stores to site of works at all level including cost of labour, material, giving satisfactory hydraulic testing etc. (Tyton Joint) 250mm	70.00	Rmt.	
17.	Providing and cast in situ C.C. in grade M-20 (Proportions as per mix design or as per table 9 of IS: 456:2000 in masses by of wight batching) using granite, quazite trap metal of size 6 mm to 20 mm for RCC Work, including scaffolding centering, formwork, needle vibrated	12.96	Cum.	

18.	consolidating, curing complete upto 6m depth or height (excluding cost of reinforcement and neat finishing) with centering and shuttering/deshuttering etc. complete for structure other than water retaining (Below G.L.) Without Water proffing chemical Thrust Block for Bend Supplying cutting, bending, binding	0.66	MT.	
10.	and placing in position steel as per plan and design and as per ISS 2502 including cost of steel and binding wire for reservoirs/structures only including lift up to 6 meter height or depth below G.L. for all diameters Do-Thermo mechanically treated (TMT)bars Fe-500 grade for all diameters.	0.00	WI	
19.	Refilling the pipeline trenches including ramming, watering, consolidating desposal of surplus stuff as directed within a radius of 3 km.	275.00	Cum.	
20.	Construction of granular sub-base by providing close graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401.	63.00	Cum.	
21.	Erection of air valve riser by installing new GI pipe of medium duty 4 mt length with necessary CI fitting such as flange of appropriate size, nut bolts and embedded the pipe in R.C.C M 20 with offset of 150 mm around pipe with necessary reinforcement etc. complete. Air Valve 50 mm Dia 250mm	1.00	Cum.	

Terms & conditions are as under:-

- 1. The rates quoted by the contractor/agency shall include all taxes including GST and nothing extra shall be payable on account of taxes for the work executed.
- 2. Sealed envelope should be superscribed word "Laying Sewerage Pipe line from SPS-7 to Ring Road Crossing near Ekdant Square in SMC Area".
- 3. The Bidder should submit the Experience Certificate of Civil /Water Supply/ Sewerage Works.
- 4. The Bidder should submit the PAN Card, GST and Copy of Valid Registration of appropriate classes.
- 5. The work should be completed within the prescribed time limit given by this Department.

- 6. The payment will be after full satisfaction of the representative of the Department.
- 7. The Agencies/Contractors should quote their rates in their own letter pad OR on plain paper with their rubber stamp.
- 8. The rates should be valid up to 31/12/2025.
- 9. Tender Fees of Rs.500/- should be submitted in favour of the undersigned (Chief Officer, Silvassa Municipal Council) in the form of a Demand Draft.
- 10. EMD for an amount of Rs. 13,050/- (Rupees Thirteen Thousand Fifty Only) should be submitted in favour of the undersigned (Chief Officer, Silvassa Municipal Council) in the form of Demand Draft/Fixed Deposit Receipt.
- 11. The Tenders shall be considered invalid and non-responsive for non-submission of any document stipulated herein. (Tender Fees, EMD)
- 12. The tender form is also available on website address https://dnh.gov.in/#Tenders and https://ddd.gov.in/#Tenders which can be downloaded and used for submitting the tender in the manner prescribed above along with the cost of the tender document and EMD.
- 13. The intending Contractors/ bidders should submit their documents by RPAD/Speed post or by hand to the Silvassa Municipal Council, Silvassa office. However, the tender inviting authority shall not be responsible for any postal delay/lost of documents demanded. The said documents can also be deposited in the Tender Box kept at the office of the undersigned on or before 06/10/2025 up to 01.00 hrs.
- 14. The tenders shall be opened on 06/10/2025 at 02:00 Hrs. in the presence of the bidders if any.
- 15. The Department of Silvassa Municipal Council reserves their right to accept or reject any or all bids without giving any reason thereof is reserved by the undersigned.

Sd/-Chief Officer Silvassa Municipal Council Silvassa

Copy to:-

- 1. The President, Silvassa Municipal Council, Silvassa, for kind information, please.
- 2. All Head of Office, D&NH, Silvassa, for kind information and vide publicity.
- 3. The Assistant Director (IT), DNH, Silvassa with request to uploading in DNH Administration Website and Silvassa Municipal Council official website (www.smcdnh.nic.in).
- 4. Notice Board.