



## SWAMI VIVEKANAND NATIONAL INSTITUTE OF REHABILITATION TRAINING AND RESEARCH

(Ministry of Social Justice & Empowerment,  
Department of Empowerment of Persons with Disabilities, Govt. of India)  
OLATPUR, P.O: BAIROI, DIST: CUTTACK (ODISHA) Pin: 754010.  
Tel. No: 0671-2805552, 2805 778, FAX: 0671 2805862.  
Website: [www.svnirtar.nic.in](http://www.svnirtar.nic.in)  
E-mail: [nirtar@nic.in](mailto:nirtar@nic.in) & [svnirtar@gmail.com](mailto:svnirtar@gmail.com)

Tender No- AD 7A 38

Date:19.05.2025

### **TENDER NOTICE**

FOR

Work of Construction for Shelter for Sensory Path at SVNIRTAR, Olatpur.

Name of work	Last Date and time of submission of Tender	Date and time of opening of Tender
Construction for Shelter for Sensory Path at SVNIRTAR, Olatpur	28.05.2025 at 12:00 hrs.	28.05.2025 at 14:00 hrs.

Quotations are invited from Civil contractors possessing valid license, who have executed civil works for other Government departments/ Public sectors/ Reputed Organizations, for execution of the above work. So as to complete the same within specified time period.

Sd/-

**Officer-in-charge  
Construction & Maintenance Division**



## SWAMI VIVEKANAND NATIONAL INSTITUTE OF REHABILITATION TRAINING AND RESEARCH

(Ministry of Social Justice & Empowerment,  
Department of Empowerment of Persons with Disabilities, Govt. of India)  
OLATPUR, P.O: BAIROI, DIST: CUTTACK (ODISHA) Pin: 754010.  
Tel. No: 0671-2805552, 2805 778, FAX: 0671 2805862.  
Website: [www.svnirtar.nic.in](http://www.svnirtar.nic.in)  
E-mail: [nirtar@nic.in](mailto:nirtar@nic.in) & [svnirtar@gmail.com](mailto:svnirtar@gmail.com)

---

### GENERAL INSTRUCTIONS AND TERMS AND CONDITIONS

1. Work has to be completed within 20 days from the date of receipt of work order.
2. Price to be filled up in the prescribed format at Annexure-A clearly both in figures as well as in words. Any ambiguity in quoting the rates shall disqualify the bidder.
3. The rates are to be quoted in Indian currency only. The rates and taxes etc. will remain unchanged throughout the contract period.
4. Bidder must have valid GSTIN.
5. SVNIRTAR would award the contract either for all the items or some of the items mentioned in the Annexure-A. The requirements may be altered by SVNIRTAR, as and when required depending upon the situation.
6. No residential accommodation can be provided to the contractor or his team of workers during execution of work.
7. The contractor shall use own tools, equipments etc. as required for the executing the work.
8. The contractor is responsible for due compliance of laws/ norms relating to safety during execution of work. The entire risk and responsibility pertaining to this contract regarding the safety & security of men, materials & machine shall rest on the contractor.
9. The contract shall be covered by Contract Labour (Regulation and abolition) Act 1970 and Contract Labour (Regulation and abolition) Central Rule 1971 with all amendments.
10. In case of breach of any laws, acts, rules mentioned above or any terms of contract mentioned herein, the contract shall be cancelled automatically.
11. The contractor must have sufficient & competent work force to do the works promptly.
12. The contractor shall execute the contract through own work force. Sub-contracting will not be allowed.
13. Work will be executed as per instructions of Engineer-in-charge.
14. Engineer-in-charge shall have the right to stop the execution of work at any stage or time, if the quality of work is found inferior, if the progress of work slower or if the work is not executed as per specifications / instructions of Engineer-in-charge.
15. The contractor shall not cause any damage to the work, nor shall hinder other contractors' works. The cost of any damage done by the contractor to the existing infrastructure of the Institute or other contractors' works, shall be borne by the defaulter with additional penalty as decided by the Director, SVNIRTAR.
16. Execution work and installation of fittings etc. (as per work order) is the entire responsibility of the contractor. No extension of time shall be allowed for the completion of work. Penalty of 1% of value of contract shall be levied for every week or part thereof towards delay in completion of work.

17. Payment shall be released approximately within 30 days only after satisfactory execution of work as per terms of contract and submission of bill. Taxes/ duties, as applicable, shall be deducted at source.

18. In case the contractor commits any breach of contract, the Institute may at any time by Notice in writing summarily terminate the contract without compensation to the contractor for any reason.

19. PERFORMANCE SECURITY:

- The contractor shall provide warranty of 6 months from the date of completion of work. In case of any defect found during the warranty period, the contractor shall promptly rectify the defects within 7 days of verbal/written intimation, as per instructions of the Engineer-in-charge

- in case any defect found in the executed work during the warranty period, the contractor shall rectify the same immediately at his own cost.

- in case of failure in executing the work or providing repair/maintenance service during the warranty period, as per terms of contract, the contract shall be terminated and the Security Deposit shall be forfeited.

20. DISPUTES & ARBITRATION:

a) All the disputes relating to the meaning and instructions under this contract hereinbefore mentioned shall be referred to the High Court of Odisha, Cuttack and any decision in this regard would be final for both the parties.

b) Director of Swami Vivekanand National Institute of Rehabilitation Training & Research (SVNIRTAR) reserves the right to cancel or reject any one or all the offers without assigning any reason thereof.

**Sd/-**

**Officer-in-charge  
Construction & Maintenance Division**

The bidder has to sign below as a token of acceptance of the above terms and conditions.

Authorized signatory with seal and date :

Name of bidder/ firm with complete postal address :

**ANNEXURE – A****BOQ**

The bidder has to be quote rates as per format given below. After filling up this form, please put your signature, seal and date.

Sl. No.	Description of work	Unit	Quantity	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm. on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	Cum	2.91		
2	GI Pipe square/circular work (cutting, fixing with required SS Nut & Bolts, GI plate etc. 80 mm, 50 mm, 25 mm Square/ Circular pipes.	Kg	1045.64		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40	Cum	3.89		
4	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	Sqm.	8.64		
5	Providing and fixing pre coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 Microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 meter or as desired by Engineer In-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape Wherever required.	Sqm	98		
6	Providing and fixing pre coated galvanized steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self-drilling/ self-tapping screws complete	Rm	14		
Total :					
Taxes (if any) :					
Grand Total : (in words) ... ..					

Authorized Signatory with Seal and date