तालुका आरोग्य अधिकारी कार्यालय
ता.सावंतवाडी

ई-मेल - tmosawantwadisindhu@gmail.com

जा.क्र.ताआअका/दरपत्रक नोटीस/ 677 /२०२६, तालुका आरोग्य अधिकारी कार्यालय, ता.सावंतवाडी, दिनांक - २८/१०/२०२६

30

दरपत्रक मागणी नोटीस

तालुका आरोग्य कार्यालय, सावंतवाडी अंतर्गत येणा-या BPHU सावंतवाडी च्या इमारतीमध्ये खालील तपशिलाप्रमाणे वाटरपुफ प्यावुडमध्ये एक्झुकेटीव् टेबल, ऑफीस टेबल व रेकॉर्ड ठेवण्यासाठी स्टोअरेज तयार करुन घेणेचे आहे. सदरचे एक्झुकेटीव् टेबल, ऑफीस टेबल व टेबल जवळ स्टोअरेज तयार करुन देणेकरिता इच्छुक दरपत्रक धारकांकडून खालील तपशिलात नमूद केलेप्रमाणे बंद लखोटयात दरपत्रके मागविणेत येत आहेत.

अ. क्र.	तपशील			मक्तेदाराने सर्व करासहीत व खर्चासहीत भरावयाचा दर
	तालुका आरोग्य कार्यालय, सावंतवाडी अंतर्गत येणा-या BPHU सावंतवाडी च्या इमारतीमध्ये खालील तपशिलाप्रमाणे फर्निचर साहित्य तयार करणे	टेबल संख्या	अंदाजपत्रकिय किंमत	दरपत्रक देताना सोबत जोडणेत आलेल्या अंदाजपत्रकाप्रमाणे वेगवेगळे Item प्रमाणे वेगवेगळे दर सादर करणेत यावा. GST रक्कम स्वतंत्रपणे नमुद करावी
1	Office Executive Table With L Shape Storage (Material Water Proof Playwood)	1	रु.3,56,246/- (Including GST)	
2	Office Table (Material Water Proof Playwood)	12		
3	Mediem Height Storage (Material Water Proof Playwood)	2		

इच्छुक दरपत्रक धारकांनी सदरची दरपत्रक नोटीस प्रसिध्द झालेपासून 10 दिवसांपर्यत म्हणजेच दिनांक 12/11/2026 रोजी दुपारी 03.00 वाजेपर्यत विहित नमून्यात परिपूर्ण दरपत्रक बंद लखोटयातून या कार्यालयास समक्ष आणून अथवा डाक सेवाव्दारे सादर करावयाची आहेत. मुदतीत प्राप्त दरपत्रकांची छाननी करुन अटी व शर्तीपूर्ण झालेली दरपत्रके खोलून तुलनात्मक तक्त्याच्या आधारे किफायतशीर दरपत्रक धारकला पुढील आदेश देणेत येईल. BPHU सावंतवाडीमध्ये तयार करणेत येणा-या फर्निचरचा आराखडा व अंदाजपत्रक (Plan & Estimate) कार्यालयात उपलब्द आहे. कार्यालयीन वेळेत पाहणेस मिळेल.

<u>दरपत्रकाच्या अटी व शर्ती</u>

01) दरपत्रक सादर करतेवळी दरपत्रकासोबत शासकिय संस्थेमार्फत दिलेला नोंदणी दाखला/ जीएसटी नोंदणी प्रमाणपत्र तसेच नोंदणीपत्रकावर नमूद मालकाचे पॅनकार्ड झेरॉक्स सोबत जोडावयाचे आहेत. दरपत्रक सोबत सादर करावयाच्या बंद लखोटयांत सदरची नोंदणी प्रमाणपत्र व मालकाचे पॅनकार्ड झेरॉक्स सोबत सादर करणे आवश्यक आहे अन्यथा सदरची दरपत्रक नामंजूर करणेत येतील.

02) वरील तपशीलात नमूद फर्निचर साहित्य तयार करावयाचा आराखडा व अंदाजपत्रक उपलब्द आहे. ज्या दरपत्रक धारकाचे दरपत्रक मंजूर होईल त्यांना कळवीण्यांत येईल. त्यानुसार ठरवून दिलेल्या वेळेत सदरचे काम पुर्ण करुन देणेचे आहे. मंजुर दरपत्रकानुसार अतीरिक्त कोणत्याही प्रकारचे चार्जेस अदा केले जाणार नाही. मंजुर दरपत्रकातील दर हे 31 मार्च 2027 पर्यंत राहतील.

03) दरपत्रक सादर करणेच्या शेवटच्या दिवशी दुपारी 3.00 वाजेपर्यन्त दरपत्रक स्वीकारली जातील इतर दिवशी कार्यालयीन वेळत पोस्ट अथवा हाती स्वीकारली जातील.

04) मंजूर दरपत्रकानुसार सदर काम पूर्ण झालेवर सर्व करांसहित झालेल्या कामाचे देयक त्वरीत कार्यालयास सादर करणे आवश्यक आहे. झालेल्या कामाच्या प्रत्यक्ष पहाणीनुसार, तसेच मा.जिल्हा आरोग्य अधिकारी कार्यालयाकडील पायाभुत सुविधा कक्ष (NHM), आरोग्य विभाग, जि.प.सिंधुदुर्ग यांचेकडील मुल्यांकणानुसार व दरपत्रकातील नमूद दरानुसार देयक बरोबर असल्याची पडताळणी करुन शासकीय प्रचलीत दरनुसार टी.डी.एस वजावट लागू असल्यास कर वजावट करुन देयकाची रक्कम संबधीत मक्तेदाराच्या बॅक खातेवर NEFT प्रणालीनुसार जमा करणेत येईल.

06) विहित मुदतीत आदेश दिलेपासून काम पुर्ण न केल्यास शासन नियमानुसार देय दंड देयकामधून वसूल केला जाईल.

07) मुदतीत प्राप्त न होणारी एक अगर सर्व दरपत्रके नाकारण्याचा अधिकार तसेच सर्व दरपत्रक प्रकीया रदद करण्यांचा अधीकार खाली सही करणार यांनी राखुन ठेवला आहे.

30/10/2026

तालुका आरोग्य अधिकारी (गट-अ)
ता. सावंतवाडी, जि. सिंधुदुर्ग

<u>दरपत्रक मागणी नोटीस लावण्याचे ठिकाण</u>

01) तालुका आरोग्य अधिकारी, सावंतवाडी नोटीसबोर्ड
02) www.nrhm.maharashtra.gov.in
03) www.arogya.maharashtra.gov.in

<u>वरील संकेतस्थळावर दरपत्रक नोटीस प्रसिध्द झालेल्या तारखेपासून 10 दिवसाच्या मुदतीत दरपत्रक स्वीकारली जातील याची नोंद घ्यावी.</u>

NATIONAL RURAL HEALTH MISSION
राष्ट्रीय ग्रामीण स्वास्थ्य मिशन
(2005-2012)

NATIONAL HEALTH MISSION

I.D.W

SINDHUDURG

Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.

Estimated Cost : 3,56,246.00

DETAILED ESTIMATE

प्रति,

मा. तालुका आरोग्य अधिकारी
तालुका सावंतवाडी

विषय :- अंदाजपत्रक सादर करीत असलेबाबत....

महोदय,

राष्ट्रीय आरोग्य अभियान अंतर्गत पायाभुत सुविधा विकास कक्ष सिंधुदुर्गकडुन **Providing & Fixing Furniture at BPHUSawantwadi Dist - Sindhudurg** इमारत बांधणेचे अंदाजपत्रक तयार केले असून सदर अंदाजपत्रकास तांत्रिक मान्यता मिळणेसाठी सविनय सादर.

अ.क्र.	कामाचे नाव	अंदाजपत्रकीय रक्कम
१.	Providing & Fixing Furniture at BPHUSawantwadi Dist - Sindhudurg.	रु. ३,५६,२४०/-

उपअभियंता
पायाभुत सुविधा विकास कक्ष,
राष्ट्रीय आरोग्य अभियान, सिंधुदुर्ग

ESTIMATE

Division	:- NHM, Health Department Z P Sindhudurg
Sanctioned Estimate	:-
Fund Head	:-
Major Head	:-
Minor Head	:-
Service Head	:-
Departmental Head	:- IDW - NHM

Estimate framed in the office of the Deputy Engineer Work's Division,Health Department Zilla Parishad Sindhudurg of the probable expenses that will be incurred.

Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.

Rs. 356246.00

Admisistratively Approved under .....

Technically Sanctioned under Date :-

Estimate prepared by Shri. B.P.Patil, Junior Engineer, NHM - IDW

Checked By Shri. A. R.Fere, Dy Engg. NHM - IDW

AnyScanner

Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.

RECAPITULATION SHEET

	Cost of work portion (Civil work)		Rs.=	**299236.00**
1	Add for Electrification Work . (AC2Nos)		Rs.=	0.00
2	Govt. Insurance	**0.5%**	Rs.=	1496.18
3	Contingencies (Lumpsum)		Rs.=	1651.00
4	GST SGST - 9%		Rs.=	26931.24
5	GST CGST - 9%		Rs.=	26931.24
		Total Amount =		**356245.66**
		Total Amount in Rs =		**356246.00**

Junior Engineer
National Rural health Missio
Zilla Parishad,Sindhudurg

Deputy Engineer
National Rural health Missio
Zilla Parishad,Sindhudurg

Technically Sanctioned For ₹ 2,99,236/-
Rupees Two Lakh Ninty Nine Thousand
Two Hundred Thirty Six only.
under NRHM. Reg. No. 07
for - 2026 / 2027

Deputy Engineer
National Rural health Missio
Zilla Parishad,Sindhudurg

SCAN AnyScanner

Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.

ABSTRACT

Item No.	Description Of Items.	Quantity	Rate	Unit	Amount
1	Executive Table @ 2250Lx2100Dx750HT including Low Height Credestal @ 1200Lx450Dx650HT Providing & Fixing of Table @ 2250Lx2100Dx750HT TOP & GABLE END to be made of Membrane finish with soft water fall	1.00	42635.00	Nos	**42635.00**
2	Executive's Table @ 1800Lx900Dx750HT Providing & Fixing of Table @ 1800Lx900Dx750HT - TOP & GABLE END to be made of Membrane finish with soft water fall edges & curved panel & Decorated Anodized section	12.00	17231.00	Nos	**206772.00**
3	Full Height Steel Storage @ 750Lx450Dx2100HT Providing and fixing Openable Steel Storage of 750 x 450 x 2100Ht, with 4 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA,	1.00	18925.00	Nos	**18925.00**
4	Medium Height Steel Storage @ 750Lx450Dx1200HT Providing and fixing Openable Steel Storage of 750 x 450 x 1200Ht, with 2 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA,	2.00	15452.00	Nos	**30904.00**
5	Low Height Openable Storage @ 900Lx450x750HT Providing and fixing Openable Steel Storage of 900 x 450 x 750Ht, with 2 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA,	0.00	12646.00	Nos	**0.00**
6	Public Seating Chair. - 3 Seater Providing and Fixing 3 seater Public seating chair made of complete metal with Legs in Crome finish and seates in silver powder coating finish...51.44	0.00	18056.00	Nos	**0.00**
7	Stool for Lab and Class-IV Providing and fixing 4 legged Lab stool, Legs made of 16 Guage 45 MM Outer dimension MS Pipe, Duly painted, With a 304 Grade Stainless steel 12 inch wide seat with a 1 inch collar,	0.00	2617.00	Nos	**0.00**
			Total Amt=		**299236.00**
			Say Rs=		**299236.00**

Junior Engineer
National Rural health Mission
Zilla Parishad,Sindhudurg

Deputy Engineer
National Rural health Mission
Zilla Parishad,Sindhudurg

AnyScanner

	Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.						
SR Nos	**MEASURMENT SHEET**						
1	Executive Table @ 2250Lx2100Dx750HT including Low Height Credestal @ 1200Lx450Dx650HT Providing & Fixing of Table @ 2250Lx2100Dx750HT TOP & GABLE END to be made of Membrane finish with soft water fall edges & curved panel & Decorated Anodized section MODESTY PANEL to be made of 18 mm thick Prelaminated particle board with PVC edge band. INCLUDING CREDESTAL @ 1200L X 450D X 650H :- To be made out of Membrane Finish (2 Openable Shutter & 3 Drawer Pedestal in between) as per drawing. ...51.24						
	For Executive Table						
	For THO Cabin	1	1.00			1.00	
					Total Qty=	**1.00**	**Nos**
2	Executive's Table @ 1800Lx900Dx750HT Providing & Fixing of Table @ 1800Lx900Dx750HT - TOP & GABLE END to be made of Membrane finish with soft water fall edges & curved panel & Decorated Anodized section MODESTY PANEL to be made of 18 mm thick Prelaminated particle board with PVC edge band as per drawing ...51.21						
	For As office Table						
	For Office Staff	12	1.00			12.00	
					Total Qty=	**12.00**	**Nos**
3	Full Height Steel Storage @ 750Lx450Dx2100HT Providing and fixing Openable Steel Storage of 750 x 450 x 2100Ht, with 4 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA, 4 Shutter to be mounted with the help of cup hinges, and 4 adjustable. levelers, enitre storage in powder coated finish with 60 to 80 microns as as per drawing...51.37						
	For Full Height Steel Storage						
	For THO Office	1	1.00			1.00	
					Total Qty=	**1.00**	**Nos**
4	Medium Height Steel Storage @ 750Lx450Dx1200HT Providing and fixing Openable Steel Storage of 750 x 450 x 1200Ht, with 2 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA, 2 Shutter to be mounted with the help of cup hinges, and 4 adjustable levelers, enitre storage in powder coated finish with 60 to 80 microns. with 25 mm. thk. as per drawing..51.36						
	For Medium Height Steel Storage						
	For Main+ Internal Door	2	1.00			2.00	
					Total Qty=	**2.00**	**Nos**
5	Low Height Openable Storage @ 900Lx450x750HT Providing and fixing Openable Steel Storage of 900 x 450 x 750Ht, with 2 adjustable shelves, Complete body & shutter made in 0.8 mm thick & Top in 2 mm thick CRCA, 2 Shutter to be mounted with the help of cup hinges, and 4 adjustable levelers, enitre storage in powder coated finish with 60 to 80 microns. with 25 mm. thk additional Top on top of storage as as per drawing..51.35						
	For Low Height Steel Storage						
	For Lead Sheet 1mm Thick = 11.40 kg/Smt MS						

	Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.						
SR Nos	**MEASURMENT SHEET**						
	For Main+ Internal Door	2	1.16		1.60	0.00	
					Total	0.00	Smt
		1	0.00	11.40	Kg/Smt	0.00	Kg
					Total Qty=	**0.00**	**Kg**
6	Public Seating Chair. - 3 Seater Providing and Fixing 3 seater Public seating chair made of complete metal with Legs in Crome finish and seates in silver powder coating finish…51.44						
	For 3 Seater Public Seating Chair						
		3	1.00			0.00	
					Total Qty=	**0.00**	**Nos**
7	Stool for Lab and Class-IV Providing and fixing 4 legged Lab stool, Legs made of 16 Guage 45 MM Outer dimension MS Pipe, Duly painted, With a 304 Grade Stainless steel 12 inch wide seat with a 1 inch collar, Height adjustment via a screw. as per design and drawing and instructions of Engineer in charge...51.51						
	For Four Leged Lab Stool						
	For Main+ Internal Door	2	1.00			0.00	
					Total Qty=	**0.00**	**Nos**

Junior Engineer
National Rural health Mission
Zilla Parishad,Sindhudurg

Deputy Engineer
National Rural health Missio
Zilla Parishad,Sindhudurg

SCAN AnyScanner

Name Of Work :-Providing and fixing Furniture at BPHU Unit at Sawantwadi Dist-Sindhudurg.

Rate Analysis

RA Item No.	Brief Description Of Items	SSR Page No./ Item No.	SSR Rate 2022-23	Royalty of Sand	Net Rate after Deduction	Lead Charges					Total Lead	Net Rate
						Material required	Material required per unit	Unit	Extra Lead	Lead Amount		
1	2	3	4	6	7	9	10	11	12	13	14	16
1	Executive Table @ 2250Lx2100Dx750HT including Low Height Credestal @ 1200Lx450Dx650HT Providing &	51.24	42635.00	0.00	42635.00			Nos				42635.00
2	Executive's Table @ 1800Lx900Dx750HT Providing & Fixing of Table @ 1800Lx900Dx750HT - TOP &	51.21	17231.00	0.00	17231.00			Nos				17231.00
3	Full Height Steel Storage @ 750Lx450Dx2100HT Providing and fixing Openable Steel Storage of 750 x 450 x 2100Ht, with 4 adjustable	51.37	18925.00	0.00	18925.00			Nos				18925.00
4	Medium Height Steel Storage @ 750Lx450Dx1200HT Providing and fixing Openable Steel Storage of 750 x 450 x 1200Ht, with 2 adjustable	51.36	15452.00	0.00	15452.00			Nos				15452.00

Junior Engineer
National Rural health Mission
Zilla Parishad,Sindhudurg

Deputy Engineer
National Rural health Mission
Zilla Parishad,Sindhudurg

Scanned with AnyScanner