**Building Type**: Group Housing

Climate Zone : Composite
Area : 5040 m2

WWR : 9.12
Conditioned Area: 4000 m2
Occupancy Type : 24 hours

**ECBC Compliance:** Whole building simulation method (**ECBC 2007**).

**Baseline EPI**: 77.26 KWh/m²/year **Proposed EPI**: 73.18 KWh/m²/year

% Energy saving: 5.28%
Payback period : 13 years

#### **HVAC Specifications**

BEE 5 star rated split AC

# **Piping and ductwork**

System Description: 20 mm thick Nitrile

Rubber

R value: R value of insulation: 0.35,

Thickness of insulation 13 mm.


## Air leakage

Envelope is sealed, caulked, gasket or weather-stripped.

## **Envelope Sealing:**

seal, caulk, gasket, or weather-strip the following areas of the enclosed building envelope to minimize air leakage ECBC requirement of 20% hot water through solar water heaters

#### TRANSIT FLATS NUH (HARYANA)



## PROJECT SUMMARY

The transit flat building is five storied building which will serve as residential quarters. The longer axis of the building is in North- South direction.

#### **BUILDING ENVELOPE**

Opaque wall: 12 mm Plaster + 230 mm

Brick wall + 12 mm Plasters

U-value: 1.80 W/m<sup>2</sup>K

Assembly thickness: 254 mm:

**Roof Assembly:** 10mm tiles + 50 mm Cement screed + 150mm RCC + 12 mm

Cement Plaster

U-value: 2.65 W/m<sup>2</sup>K

Assembly thickness: 222 mm

**Glazing type 1:** Single Glazed Unit

U-value: 4.5 W/m<sup>2</sup>K, SHGC: 0.31, VLT:

18%

Glazing type 2 : DGU( Double Glazed

Unit

U-value: 2.8 W/m<sup>2</sup>K, SHGC: 0.28, VLT:

21%

Lighting Power Density

Space Function Method

Bedroom / Drawing Room :9 W/m2

Lobby : 9 W/m2
Toilets : 7 W/m2

Kitchen : 10 W/m2

Common Areas : 4 W/m2

Fixtures - :LED Bulbs

**Occupancy Sensors**: in corridors, toilets, offices and conference rooms


**Exterior Lighting Details** 


Fixtures with minimum efficacy of 80

lumens/watt.

## **Energy Consumption Comparison between Base Case and Proposed Case**

Consumption	Heating (kWh)	Cooling (kWh)	Area Lighting (kWh)	Fans (kWh)	Misc Equipment (kWh)	Hot Water (kWh)	Total (kWh)
Baseline	2.59	135.33	116.08	25.93	41.46	62.84	383.23
Proposed	20.03	171.91	33.16	39.16	41.46	63.13	368.84





Proposed office building has been modelled using the e-QUEST energy simulation software which is able to model energy flows on hourly basis for the entire year. Provided are the charts indicating the steps flow of 'Whole Building Energy Performance Process. Summarizing the output results of energy simulation into following points:

• 5.28% energy saving is achieved by following ECBC compliance.

Case	Cost		
Conventional building	Rs. 14851072		
Prescription based	Rs. 21807662		
Whole building	Rs. 19373130		
simulation based			

Incremental cost percentage as compared to conventional case.

Prescription based: 31.8 %

Whole building simulation based: 30 %

The difference between proposed cost through whole building energy simulation method and conventional method would be Rs. 4522058. On the other hand cost difference between proposed cost through prescription based method and conventional cost would be Rs. 6956590.

The annual electricity saving in energy is

Rs. 1395911.65 @ Electricity tariff Rs. 5/ kWh.

**Payback period: 3.29 years** (whole building simulation method.

Payback period: 4.98 years (prescription based

method)