AKTU CODE: 162

An ISO 9001:2008 Certified Institute

SHAMBHUNATH INSTITUTE OF ENGINEERING & TECHNOLOGY (SIET)

(Approved by AICTE, New Delhi & Affiliated to Dr. A.P.J. Abdul Kalam Technical University, Lucknow) ET/GSPL-MMS/001/1 23/11/2020

D	-1		÷	
n	61	u	2	

Date																		
Date		٠	• •	•	۰	٠		٠		٠	*	٠	٠	٠	٠	۰	٠	

TO WHOMSOEVER IT MAY CONCERN

We have been offered various configuration/designs of solar photovoltaic Module Mounting structure (MMS) as per the following drawings for evaluation as per IS 875-1964.

These designs were evaluated by using Staad Pro report for various parameters described in IS 875-1964 & IS-800 and found to be having a factor of safety of 2.0 or higher at wind load of 150 kms/hour.

Structure size	Drawing Number	Calculated Factor of Safety as per IS 875-1964
5 Module	GSPL/5-SPV/MMS	
6 Module	GSPL/6-SPV/MMS	The elements have been
8 Module	GSPL/8-SPV/MMS	designed using guideline as per IS 875-1964, the attached report
9 Module	GSPL/9-SPV/MMS	shows that actual stresses in the elements are at least 2 time less
10 Module	GSPL/10-SPV/MMS	than allowable stresses. Hence it has 2 FOS.
11 module	GSPL/11-SPV/MMS	IIas 2 FOS.

We therefore certify that the Solar Photovoltaic Module mounting structures as per aforementioned design and drawings numbers fully comply with the requirements of IS 875-1964 as are suitable for withstanding a wind load of 150 kms/hour.

Certified by

Vinay Mishoo HOD - Civil

Post:

23/11/2020

Location: Allahabard



Institute Address : Jhalwa, Prayagraj - 211 015 Whatsapp/Mobile : 7388098055

AKTU CODE: 162

STELLA ST

Ref .:

An ISO 9001:2008 Certified Institute

SHAMBHUNATH INSTITUTE OF ENGINEERING & TECHNOLOGY (SIET)

(Approved by AICTE, New Delhi & Affiliated to Dr. A.P.J. Abdul Kalam Technical University, Lucknow)

SIET/GSPL-MMS/001

D3(4)	/202	0	
GOLE!	1 60 34 60)	V.cress.	

To, M/s Gautam Solar Private Limited D-120/121 Okhla Industrial Area, Phase-I, New Delhi-110020

Subject: Evaluation of module Mounting structures.

Dear Sir,

You have submitted following drawings for various types/designs of Solar Photovoltaic Module mounting structures for evaluation of their suitability for being a wind Load of 150 Kms/hour

Sr. No.	Structure Size	Departing Nous Land
1	5 Module MMS	Drawing Number
2	6 Module MMS	GSPL/5-SPV/MMS
3	8 Module MMS	GSPL/6-SPV/MMS
4	9 Module MMS	GSPL/8-SPV/MMS
5	10 Module MMS	GSPL/9-SPV/MMS
6		GSPL/10-SPV/MMS
U	11 Module MMS	GSPL/11-SPV/MMS

The same have been evaluated as per IS 875-1964 for bearing a wind load of 150 kms/hour and we are herewith enclosing the following documents:

- Certificate confirming that the drawings meet the requirements of IS 875-1964 for a wind load of 150 kms/hour.
- 2. Our analysis of each of these structures.
- 3. Certified copy of each of the aforementioned drawings, including the drawing for the foundation.
- 4. Details of various structural design and certification projects undertaken by the structural engineering department of our college.
- 5. Background information of our college.

Name: Vinay Mishra

Post: HOD - CIVIL

Date: 23/11/2020

Location: Allahabad

Institute Address: Jhalwa, Prayagraj - 211 015 Whatsapp/Mobile: 7388098055

An ISO 9001:2008 Certified Institute



SHAMBHUNATH INSTITUTE OF ENGINEERING & TECHNOLOGY (SIET)

(Approved by AICTE, New Delhi & Affiliated to Dr. A.P.J. Abdul Kalam Technical University, Lucknow)

Ref .:

SIET/GSPL-MMS/001/2

Date :

23/11/2020

We have compared the design of the structures which are provided in the tender no. NIT/Bid Document No. EESL / 06 / 2019-20 / KUSUM / SWPS /Phase-1/ Off Grid /192007012 dt 18-07-2019 (Section-4; Page 19 of 102 Clause 3.5.3) which we call as the "indicative MNRE design" with the structure foundation designs as per following drawing numbers which we call the 'ALTERNATE design'

Sr. No.	Structure Size	Drawing Number		
1	5 Module MMS	GSPL/5-SPV/MMS		
2	6 Module MMS	GSPL/6-SPV/MMS		
3	8 Module MMS	GSPL/8-SPV/MMS		
4	9 Module MMS	GSPL/9-SPV/MMS		
5	10 Module MMS	GSPL/10-SPV/MMS		
6	11 Module MMS	GSPL/11-SPV/MMS		

The designs have been verified and duly certified by us vide our letter no. SIET/GSPL-MMS/001/1 dated: >13/11/2020 and that certificate should be read in conjunction with this certificate.

We hereby state the improved technical features and advantages of the Alternate design over the indicative MNRE Design.

Sr. No.	Feature	Improvement in Alternate design	Advantage/Benefit
1	Factor of safety	MNRE design specifies the structure should be suitable for wind load of 150 Kms/hour. The alternate design has a factor of 2.0 or higher of all the structural members considering a wind load of 150 Kms/hour on basis of 'Staad Pro' report for various parameters described in 875-	Higher Factor of safety would result in better reliability and longer life of the structure.
2	Use of all parts as per BIS standards	MNRE design has several parts as per attached table which are not as per IS 1161 whereas all the members used in ALTERNATE design are as per IS 1161 Refer annexure to this certificate	100% conformity of all parts to national standards resulting in better quality.
3	Shear force withstanding capability	The central member of MNRE design has a shear force withstanding ability of 8.0 KN/m, whereas the ALTERNATE design has a shear force withstanding ability of 11.5 KN/m, for 10 MMS design and 11.0 KN/m for 9 MMS design.	35% higher shear force withstanding ability of the central member would ensure higher strength and reliability of the ALTERNATE design.

Institute Address: Jhalwa, Prayagraj - 211 015 Whatsapp/Mobile: 7388098055



4	Shadow Free area occupied by the structures	As per MNRE design 2 Structures are required in 3 HP covering an area of 34 sq m with 02 foundations and in ALTERNATE design, a single structure is required requiring and areas of 20 sq m with 01 foundation.	30% higher land use efficiency for 3 HP Pumps.
5	Foundation suitability for sandy soils	As per MNRE, Annexure-I of circular No. F. No. 41/3/2018-SPV Division dated 17.07.2019 specifications of MMS-specification of main parts point 1. Centre shaft, suggest foundation with Base plate and direct piling foundation design. The ALTERNATE design employs piling foundation type and such type of foundation is better suited for soft and sandy soils having density lower than 1.7g/cm3	Use in multiple locations including soft and sandy soils having density lower than 1.73 g/cm3. Direct piling design is design is preferable for soft soil type like sandy soil or soil having low bearing capacity it is also provide hide uplift resistance to wind loads, the structure having piing foundations has better alignment than the structure having 4 nos. J-BOLT foundations. Alternate structure top of foundation is 200 mm above ground level, so no water logging and longer life of structure. In J-Bolt foundation structure design the whole loads are on J-Bolts which are 750 mm below ground level where in piling foundation the main pole is 850 mm below ground level which gives more stability to structure. Piling design prevents the users from installing the structures on their roof tops and other unsuitable sites.

Thus we state that the 'ALTERNATE design' of structures have several improvements over the indicative MNRE design as stated above and hence the ALTERNATE design is an improved design.



ANNEXURE TO THE CERTIFICATE

Table of materials specified for the MNRE design

Bill of Quantity for main parts of MMS for Solar Water Pumping System

SR. NO.	PART NAME	CROSS SECTION DETAILS	LENGTH (MM)	QUANTITY PER SET
A	Common for MMS for 4, 6 and	8 Modules		
1	MAIN POLE	139 OD	1500	1
2	TOP PLATE	300 OD		1
3	CLAMP WITH BLADE	75X8	380	2
4	SUPPORTING PIPES	41 OD & 33 OD		6
В	Different for MMS for 4, 6 and	18 Modules		
5	MAIN TUBE			
	4 and 6 Modules	60X60X3.6	3300	1
	8 Modules	122X61X3.6	3300	1
6	SIDE TUBE			
	4 and 6 Modules	50X50X3.6	3300	2
	8 Modules	80X40X3.2	3300	
7	Mounting Purlin			
	8 Module	80X50X15X2	2050	4
	6 Module	80X50X15X2	3100	4
	8 Module	80X50X15X2	4150	4

The following components in the table above do not confirm to IS Standards

- a) Main Pole-PIPE 139 OD and 4 mm thick-Non confirming to IS 1161
- b) Supporting Pipes-PIPE 41 OD and 33 OD-Non conforming to IS 1161
- c) Main Tube for 4 & 6 modules- TUBE 60X60X3.6, Not conforming to IS 4923

As may be seen in the drawings of ALTERNATE design, each main part of each MMS conforms to the relevant IS standards.



An ISO 9001:2008 Certified Institute



SHAMBHUNATH INSTITUTE OF ENGINEERING & TECHNOLOGY (SIET)

(Approved by AICTE, New Delhi & Affiliated to Dr. A.P.J. Abdul Kalam Technical University, Lucknow)

Ref .:

SIET/GSPL-MMS/001/2

Date :

23/11/2020

We have compared the design of the structures which are provided in the tender no. NIT/Bid Document No. EESL / 06 / 2019-20 / KUSUM / SWPS /Phase-1/ Off Grid /192007012 dt 18-07-2019 (Section-4; Page 19 of 102 Clause 3.5.3) which we call as the "indicative MNRE design" with the structure foundation designs as per following drawing numbers which we call the 'ALTERNATE design'

Sr. No.	Structure Size	Drawing Number		
1	5 Module MMS	GSPL/5-SPV/MMS		
2	6 Module MMS	GSPL/6-SPV/MMS		
3	8 Module MMS	GSPL/8-SPV/MMS		
4	9 Module MMS	GSPL/9-SPV/MMS		
5	10 Module MMS	GSPL/10-SPV/MMS		
6	11 Module MMS	GSPL/11-SPV/MMS		

The designs have been verified and duly certified by us vide our letter no. SIET/GSPL-MMS/001/1 dated: >13/11/2020 and that certificate should be read in conjunction with this certificate.

We hereby state the improved technical features and advantages of the Alternate design over the indicative MNRE Design.

Sr. No.	Feature	Improvement in Alternate design	Advantage/Benefit
1	Factor of safety	MNRE design specifies the structure should be suitable for wind load of 150 Kms/hour. The alternate design has a factor of 2.0 or higher of all the structural members considering a wind load of 150 Kms/hour on basis of 'Staad Pro' report for various parameters described in 875-	Higher Factor of safety would result in better reliability and longer life of the structure.
2	Use of all parts as per BIS standards	MNRE design has several parts as per attached table which are not as per IS 1161 whereas all the members used in ALTERNATE design are as per IS 1161 Refer annexure to this certificate	100% conformity of all parts to national standards resulting in better quality.
3	Shear force withstanding capability	The central member of MNRE design has a shear force withstanding ability of 8.0 KN/m, whereas the ALTERNATE design has a shear force withstanding ability of 11.5 KN/m, for 10 MMS design and 11.0 KN/m for 9 MMS design.	35% higher shear force withstanding ability of the central member would ensure higher strength and reliability of the ALTERNATE design.


Institute Address: Jhalwa, Prayagraj - 211 015 Whatsapp/Mobile: 7388098055




4	Shadow Free area occupied by the structures	As per MNRE design 2 Structures are required in 3 HP covering an area of 34 sq m with 02 foundations and in ALTERNATE design, a single structure is required requiring and areas of 20 sq m with 01 foundation.	30% higher land use efficiency for 3 HP Pumps.
5	Foundation suitability for sandy soils	As per MNRE, Annexure-I of circular No. F. No. 41/3/2018-SPV Division dated 17.07.2019 specifications of MMS-specification of main parts point 1. Centre shaft, suggest foundation with Base plate and direct piling foundation design. The ALTERNATE design employs piling foundation type and such type of foundation is better suited for soft and sandy soils having density lower than 1.7g/cm3	Use in multiple locations including soft and sandy soils having density lower than 1.73 g/cm3. Direct piling design is design is preferable for soft soil type like sandy soil or soil having low bearing capacity it is also provide hide uplift resistance to wind loads, the structure having piing foundations has better alignment than the structure having 4 nos. J-BOLT foundations. Alternate structure top of foundation is 200 mm above ground level, so no water logging and longer life of structure. In J-Bolt foundation structure design the whole loads are on J-Bolts which are 750 mm below ground level where in piling foundation the main pole is 850 mm below ground level which gives more stability to structure. Piling design prevents the users from installing the structures on their roof tops and other unsuitable sites.


Thus we state that the 'ALTERNATE design' of structures have several improvements over the indicative MNRE design as stated above and hence the ALTERNATE design is an improved design.










THIS DRAWRING IS THE COPYRIGHT AND THE SOLE PROPERTY OF FORM YIT MUST NOT BE COPIED IN ANY FORM WITHOUT PRIDE CONSENT OF THE COMPANY.







THIS DRAWRING IS THE COPYRIGHT AND THE SOLE PROPERTY OF FORM YITHOUT PRIOR CONSENT OF THE COMPANY.





THIS DRAWRING IS THE COPYRIGHT AND THE SOLE PROPERTY OF WITHOUT PRIDR CONSENT OF THE COMPANY.





DO NOT SCALE DRAWING ALL DIMENSIONS ARE IN MM

SUPPORTING PIPE (FOR SIDE)

Ø14.00 20.09F -32NB (ROUND PIPE) -1897, 00· 000 25, 00-20,005 9

25

25NB (ROUND PIPE) QTY - 2 NO.s ITEM - 08



DE BURR ALL SHARP EDGES . ALL PART SHOULD BE GALVANIZED

DRAWING NO. GSPL/10-SPV/MMS

DATE

CHECKED BY --HEMANT--

APPROVED BY -ANIRUDH-

---SUNIL--

NTS

SCALE DRAWN BY

STRUCTURE DRAWING FOR SPV PUMP, 10NO.s OF 300 MODULE

MATERIAL - MS

PART NAME

PART NO.


Plot No. 114, Sector-6A, IIE Ranipur SIDKUL, Haridwar - 249403 (UTTRAKHAND) Ph. 01334315551, Mob. 9810041987, 9310141982 www. gautamsolar. com

GAUTAM SOLAR PVT. LTD.

CHANGE RECORD


SR. ND


THIS DRAWRING IS THE COPYRIGHT AND THE SOLE GAUTAM SOLAR, IT MUST NOT BE COPPED WITHOUT PRIDE CONSENT OF THE COMPANY. YDBERTY YNA NI FDRM OŁ




THIS DRAWRING IS THE COPYRIGHT AND TH GAUTAM SOLAR, IT MUST NOT BE WITHOUT PRIDR CONSENT OF THE COMPANY. DE LOKW YRDPERTY YNA NI THE SOLE

DRAWING NO. GSPL/10-SPV/MMS DO NOT SCALE DRAVING ALL DIMENSIONS ARE IN MM SHEET -11/13-DATE --HEMANT--PART NAME APPROVED BY -ANIRUDH---SUNIL--PART NO. NTS - MS DRAWN BY CHECKED BY Plot No. 114, Sector-64, IIE Ranipur SIDKUL, Haridwar - 249403 (UTTRAKHAND) Ph. 01334315551, Mob. 9810041987, 9310141982 www. gautamsolar. com 0 MATERIAL SUPPORTING PIPE JOINT (BACK) 25NB (ROUND PIPE) GAUTAM SOLAR PVT. LTD. SCALE QTY - 1 NO. ITEM - 11 32NB (ROUND PIPE) STRUCTURE DRAWING FOR SPV PUMP, 10NO.s OF 300 MODULE Ø14.00-0 20, 00 25NB (ROUND PIPE) CHANGE RECORD SR. ND Ø14.00-01 20.00 1000, 00-32NB (ROUND PIPE) QTY - 1 NO.s DE BURR ALL SHARP EDGES ALL PART SHOULD BE GALVANIZED -750, 00· SUPPORTING PIPE (BACK) ITEM - 12 30,00 50 61. 59 56, 50-TES: -30, 00- 20, 00ochno log 20, 00-THE CO Engineering & ZI DMRWMRING 12 MATUAD MATUAD MITHOLING TUDHTIW COPYRIGHT AND THE SOLE MUST NOT BE COPIED OF THE COMPANY. ҮРӨПРЕРТҮ ТИ АИҮ OF FORM










THIS DRAWRING IS THE COPPRAY.


THIS DRAWRING IS THE COPPRAY.





THIS DRAWRING IS THE COPPRIGHT AND THE SOLE PROPERTY OF GAUTAM SOLAR, IT MUST NOT BE COPIED IN ANY FORM WITHOUT PRIDE CONSENT OF THE COMPANY.















DO NOT SCALE DRAVING DIMENSIONS ARE IN MM

SUPPORTING PIPE (FOR SIDE)



ITEM - 08 QTY - 2 NO.s 25NB (ROUND PIPE)



58 7 11 2 50 A W

DATE

--HEMANT--

APPROVED BY CHECKED BY

NTS

DRAWN BY

MATERIAL - MS SCALE NTS

STRUCTURE DRAWING FOR SPV PUMP, 8 NO.5 OF 300 MODULE

PART NAME -ANIRUDH-

PART NO.

Plot No. 114, Sector-6A, IIE Ranipur SIDKUL, Haridwar - 249403 (UTTRAKHAND) Ph.01334315551, Mob.9810041987,9310141982 www.gautamsolar.com


GAUTAM SOLAR PVT. LTD.


CHANGE RECORD

SR. ND

DRAVING ND. - GSPL/8-SPV/MMS

THIS DRAWRING IS THE COPYRIGHT AND TH GAUTAM SOLAR, IT MUST NOT BE WITHOUT PRIDR CONSENT OF THE COMPANY. YTA39099 YNA NI FORM COPIED COPIED JO





THIS DRAWRING IS THE COPYRIGHT AND THE SOLE PROPERTY OF GAUTAM SOLAR, IT MUST NOT BE COPIED IN ANY FORM WITHOUT PRIOR CONSENT OF THE COMPANY,

