

**KENDRIYA VIDYALAYA, ARMY CANTT., PANGODE,
TRIVANDRUM**

FORMAT OF QUOTATION

Sl. No.	Description of work (complete as specified)	Unit	Rate (₹, incl. GST)	Remarks / brand
1	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size ½ inch, 10 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
2	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size ¾ inch, 10 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
3	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 1 inch, 10 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
4	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 1¼ inch, 10 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
5	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 1½ inch, 10 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
6	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 2-inch, 6 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
7	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 2½ inch, 6 gauge including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
8	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 4 inch (4 gauge), including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
9	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 6 inch (4 gauge), including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
10	Dismantling/removal of existing GI pipe and replacement with new ISI-marked PVC pipe, nominal size 8 inch (4 gauge), including suitable fittings, clamps, jointing, testing and making good.	Per meter rate		
11	Replacement of PVC doors of toilets- materials, (2 m height, 0.7 m width) accessories, fitting and labour as per the request of competent authority.	Per door		
12	Acid wash of closets, urinals, tiles, wash area.	Per sq.ft.		
13	Supply and installation/replacement of large-size urinal, with sprinkler complete with required fixing accessories, connectors, traps and testing.	Per sq.ft.		
14	Supply and installation/replacement of water closet (Indian/Western type, as directed at site), complete with fixing accessories, connector, seal and testing. Bidder to specify type and brand.	Per piece		

15	Dismantling/removal of existing of Western closet and replacing with Indian closet- Supply and installation	Per piece		
16	Supply and installation/replacement of push cock/angle valve, complete with required accessories and testing.	Per piece		
17	Supply and installation/replacement of flush valve/flush arrangement, where directed, complete with accessories and testing.	Per piece		
18	Supply and fixing of stainless-steel floor grating, approximately 6 × 6 inch or 4 × 4 inch as directed at site, including fixing accessories.	Per piece		
19	Removal of damaged wall tiles and supply and fixing of 4 ft X 2ft replacement wall tiles, including adhesive/mortar, grouting, cutting, finishing and disposal of old tiles/debris.	Per sq. ft.		
20	Maintenance/re-fixing of existing 2 ft × 2 ft floor tiles, including lifting and re-laying where required, alignment and levelling, and filling tile joints/gaps with suitable epoxy grout; include necessary materials and finishing.	Per sq. ft.		
21	Cement plastering and making good damaged wall/chases after plumbing works, including surface finishing.	Per sq. ft.		

Name of the Firm:

Sign

Seal