



पीएम श्री केंद्रीय विद्यालय, के.रि.पु.ब., पल्लिपुरम
PM SHRI Kendriya Vidyalaya, CRPF, Pallipuram,
तिरुवनंतपुरम-695 316
Thiruvananthapuram - 695 316
दूर भाष: 0471-2750425
Website : www.crpfpallipuram.kvs.ac.in
CBSE Affiliation No. 900013

फ. 3189/ के विपीपीएम /2024-25

दिनांक: 03.03.2025

TENDER NOTICE

Tender for Retiling in Senior Secondary Computer Lab

1. Introduction

PM SHRI Kendriya Vidyalaya CRPF Pallipuram invites sealed tenders from eligible and experienced contractors for the **removal of old tiles, surface preparation, and laying of new tiles** in the computer lab. The work must be completed as per the specifications and timelines mentioned in this tender document.

2. Scope of Work

The scope of work includes, but is not limited to, the following:

1. Removal of Old Tiles:

- Carefully remove existing tiles from the computer lab floor.
- Ensure no damage to the underlying surface or surrounding areas.
- Dispose of debris and waste material as per municipal guidelines.

2. Surface Preparation:

- Clean and level the surface to ensure it is free from dust, grease, and unevenness.
- Apply a primer or adhesive as required for proper bonding of new tiles.

3. Laying New Tiles:

- Supply and lay high-quality ceramic/vinyl tiles (as specified) in the computer lab.
- Ensure proper alignment, spacing, and finishing.
- Use appropriate grouting and sealing materials.

4. Clean-Up:

- Remove all waste materials and leave the site clean and ready for use.

3. Specifications

1. Tile Specifications:

- Type: Ceramic/Vinyl tiles (non-slip, durable, and easy to clean, Matt finish).
- Size: 2x2 feet or 600cm X 600 cm as per requirement thickness 8mm.
- Total tiling area approximate 480 Sq feet outside the room and 1200 Sq feet inside the lab.
- Color: As per school's preference

2. Adhesive and Grouting:

- Use high-quality tile adhesive and grouting material suitable for the specified tiles.
- 2mm spacer
- Joint filler- Lacto crate
- Cement - Acc/ Ramco/ Sankar / UltraTech

3. Surface Preparation:

- Ensure the surface is level and free from cracks or imperfections.

4. Workmanship:

- Tiles must be laid evenly without gaps or uneven surfaces.
 - Proper curing and finishing must be ensured.
-

4. Eligibility Criteria for Contractors

1. The contractor must have a minimum of **3 years of experience** in similar tiling work.
 2. The contractor must provide proof of previous work (e.g., contracts, client references).
 3. Valid GST registration and other necessary licenses.
 4. The contractor must comply with all safety and labour laws.
-

5. Timeline for Completion

The work must be completed within **15 days** from the date of awarding the contract. Delays will attract penalties as per school policy. The work must carry out without disturbing school/ Exam.

6. Submission of Tender

1. The tender document must include:
 - Detailed work plan and methodology.
 - Itemized cost estimate must include all types of Taxes, transportation and handing charges at site end. **Fill the Annexure-A (attached)**
 - Proof of eligibility (experience, licenses, etc.).
 - Timeline for completion.
2. Tenders must be submitted in a sealed envelope, clearly marked with the tender reference number, and addressed to:

**The Principal,
PM SHRI Kendriya Vidyalaya, CRPF,
PALLIPURAM, THIRUVANTHAPURAM 695316**

3. Last date for submission: **10.03.2025**
 4. Tender opening date: **11.03.2025, 10:00 AM**
-


7. Evaluation and Award of Contract

1. Tenders will be evaluated based on:
 - Cost competitiveness.
 - Experience and technical capability.
 - Adherence to specifications and timelines.
-

2. The school reserves the right to accept or reject any tender without assigning any reason.

8. Terms and Conditions

1. Payment will be released in instalments upon completion of milestones, subject to satisfactory inspection.
2. The contractor must ensure safety measures and provide necessary safety equipment for workers.
3. Any damage to school property during the work will be the responsibility of the contractor.
4. The vender or the representative of vender must visit the site before quoting the tender.
5. The vender or the representative of vender must present the venue while opening the tender.
6. The rates quoted must include all types of Taxes and transportation and handing charges at site end.



Principal

प्राचार्य/PRINCIPAL

पीएम श्री केंद्रीय विद्यालय/PM SHRI KENDRIYA VIDYALAYA
सी आर पी एफ पल्लीपुरम/CRPF PALLIPPURAM
तिरुवनंतपुरम/THIRUVANANTHAPURAM PIN-695316

Name of the Firm with GST Number / Letter Head of the firm

Annexure-A

Date:

| Sl. No. | Particulars | Amount |
|---------|--|--------|
| 1. | Amount for removing of old broken tiles with proper disposal including GST, Handling and Labour Charges | |
| 2. | Preparation of site for laying new tiles approximate 1200 Sq feet inside the lab and 850 Sq feet outside the room including GST and Labour Charges | |
| 3. | Laying of new tiles with proper adhesive/cement etc with GST and Labour Charges | |
| 4. | Total Cost for complete work | |

Note:

- 1) Before start the work, the sample of tiles and adhesive/cement will be shown to Vidyalaya Committee.
- 2) There will be No Extra Charges

Signature with Seal and Date