



पीएम — केंद्रीय विद्यालय, के.रि.पु.ब., पल्लिपुरम
PM SHRI Kendriya Vidyalaya, CRPF, Pallipuram,
तिरुवनंतपुरम - 695 316
Thiruvananthapuram - 695 316
दूर भाष : 0471-2750425
Website : www.crpfpallipuram.kvs.ac.in
CBSE Affiliation No. 900013

फ. 3189/ के वि पीपीएम /2024-25

दिनांक: 20.03.2025

TENDER NOTICE

1. Introduction:

PM SHRI Kendriya Vidyalaya CRPF Pallipuram invites sealed tenders from reputed and experienced contractors for the construction of a Children's Traffic Park within the Vidyalaya premises. This project aims to create a safe and engaging environment for students to learn about traffic rules and road safety.

2. Scope of Work:

The scope of work includes, but is not limited to:

- 1) **The traffic park:** Must suitable for the children under the age of 11 (Eleven) years.
- 2) **Site Visit:** The contractor or representative of the contractor must visit the site and get the clear picture about the project before submitting the tender
- 3) **Site Preparation:** Clearing and levelling the designated area.
- 4) **Length and Width:** Approximately 30 meter Length one side, 5 meter width (2M one side, 2 M next side, 1M in-between)
- 5) **Construction of Miniature Roads:**
 - a. Laying concrete roads with minimum 5cm thickness
 - b. Black Tar colour floor guard painting must be done for the road and white for the boarders.
 - c. Markings: zebra crossings, lane markings, etc.
 - d. Antiskid levelled road should be maintained with proper speed breaker and traffic marking.
- 6) **Installation of Traffic Signals and Signboards:**
 - a. Supply and installation of working traffic lights, stop signs, yield signs, and other relevant road signs.
 - b. They must be removable and re-usable when needed.
 - c. Sign and symbols must be as per the Indian Standards.
 - d. Signboards must be fixed in a 1.5" round iron pipe with the height of minimum 5 feet (Five feet) from the ground level, may be fixed in a bigger pipe dug inside the ground.
 - e. Pipes must be painted with powder coated mat finish standard colour.
 - f. Sign boards must be in good quality of PVC/Metal.
 - g. Minimum 15 (Fifteen) signboards required.
 - h. Minimum 1 (One) electrical traffic light must be installed with proper electrical connection
- 7) **Maintain proper Pedestrian Pathways:** Maintain the current footpath with appropriate kerbs and ramps.
- 8) **Drainage System:** Installation of a proper drainage system to prevent water logging.
- 9) **Boundary:** Construction of a suitable boundary around the park so it may be intact.
- 10) **Any other work related to the completion of the traffic park.**
- 11) Work should not affect the daily routine of the Vidyalaya including exams.

3. Eligibility Criteria:

- The contractor must have a minimum of **3 years of experience** of work.
- Valid GST registration and other necessary licenses.
- The bidder must be a registered contractor with a valid license.
- The bidder must have all necessary tools and equipment.

4. Submission of Tender:

1. The tender document must include:
 - o Detailed work plan and methodology.
 - o Itemized cost estimate must include all types of Taxes, transportation and handing charges at site end. **Fill the Annexure-A (attached)**
 - o Timeline for completion.
2. Tenders must be submitted in a sealed envelope, clearly marked with the tender reference number, and addressed to:

**The Principal,
PM SHRI Kendriya Vidyalaya, CRPF,
PALLIPURAM, THIRUVANTHAPURAM 695316**

3. Last date for submission: **26.03.2025, 10:00 AM**
4. Tender opening date: **26.03.2025, 12:00 Noon**

5. Evaluation and Award of Contract:

1. Tenders will be evaluated based on:
 - o Cost competitiveness.
 - o Experience and technical capability.
 - o Adherence to specifications and timelines.
 - o The work may award on the total amount including GST as per the work done.
 - o The school reserves the right to accept or reject any tender without assigning any reason.

6. Terms and Conditions:

1. The work must be finished within 10 days of work order.
2. Payment will be released upon completion of the work to the satisfactory inspection.
3. The contractor must ensure safety measures and provide necessary safety equipment for workers.
4. Any damage to school property during the work will be the responsibility of the contractor.
5. After finishing the work the site must be cleared for verification taking out all belongings of the vender.
6. The vender or the representative of vender must visit the site before quoting the tender.
7. The vender or the representative of vender may present the venue while opening the tender.
8. The rates quoted must include all types of Taxes and transportation and handing charges at site end.
9. Payment will be done on the bases of actual work done after the satisfaction of the committee.
10. No extra charges will be paid.
11. TDS may be deducted if applicable.

7. Contact Information:

For any queries, please contact:

**The Principal,
PM SHRI Kendriya Vidyalaya, CRPF,
PALLIPURAM, THIRUVANTHAPURAM 695316
Ph: 0471 2750425, EMail – kv_ppm@yahoo.com**


प्राचार्य/PRINCIPAL

Name of the Firm with GST Number / Letter Head of the firm

Annexure-A

Date:

Subject: Construction of a Children's Traffic Park in the Vidyalaya

Sl. No.	Particulars	Amount
1.	Site Preparation: Clearing and leveling the designated area.	
2.	Construction of Miniature Roads: 30 meter Length one side, 5 meter width (2M one side, 2 M next side, 1M in-between) and as mention in the Tender Notice.	
3.	Installation of Traffic Signals and Signboards: Minimum 15 (Fifteen) signboards, Minimum 1 (One) electrical traffic light and as mention in the Tender Notice.	
4.	All other work related to the completion of the traffic park.	
5.	Total Cost for complete work including GST	

Note:

- 1) The work must be finished within 10 days of work order.
- 2) Payment will be done on the bases of actual work done after the satisfaction of the committee.
- 3) There will be No Extra Charges.

Signature with Seal and Date