

The Principal, PM SHRI KV Burdwan, invites sealed quotations for Civil Electrical Work from eligible vendors by 04.03.2026.
For details, please visit our website - www.burdwan.kvs.ac.in

A) Civil Work-

i) Raising the height of the approach road to the **Staff Quarters** to the newly constructed RCC Road.

S.N	Work	Technical Specification	Cost i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost
1	To raise the height of the approach road to the 3 Staff Quarters Building Entrance	Approach Road - L 28.2 ft x W 8.7 ft x 3 Nos. (at different nearby location) i) Raising the height by 1 foot on both side guard walls of the approach road by 5" Brick Wall with mortar ratio (Cement : Sand -1 : 4) ii) The sand filling by 7" iii)3" Brick Soling on top iv)Top finishing with 2 inches PCC with mortar ratio (Cement : Sand -1 : 3)	(Cost including all materials & labour) i) ii) iii) iv) v)
2	Refitting of the Iron Grill Gate by raising the Height of the fixing pillars	Pillars – 10 in x 10 in – 6 Nos. (Both sides for Grill Gate of 3 Entrances) i)Raising the Pillars height by 2 feet & after finishing plaster work, refixing the Grill Gate on the same Pillars. Plaster with mortar ratio (Cement: Sand -1 : 4)	
3	Replacement of Bib Cock / Pillar Cock (Supply & fitting at the location)	ISI / BIS Marked i) PVC ii) CI iii) CP	Provide Rate Per Piece (Cost including all materials & labour) i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost
4	Replacement of Wash Basin (Supply & fitting at the location)	ISI / BIS Marked Ceramic – L-20" x W-15" x D-5"	Do
5	Replacement of Boy's Wall-Mounted Urinal Pot with all fittings (Supply & fitting at the location)	ISI / BIS Marked Wall Mounted Ceramic Urinal – Small - L-600mm x W-300mm x D-350mm	Do

6.	<p>Exterior Weather Coat Painting Paint & Primer - ISI / BIS Marked - Paint Make / Brand - Asian Paint - Apex Ultima / Berger Paints - Weathercoat Anti-Dust / Dulux - Promise Exterior Primer Make / Brand - Asian Paint - Sparc Exterior Wall Primer / Berger - Weathercoat Exterior Primer / Dulux - Promise Exterior Primer</p>	<p>Applying two coats of synthetic (Weather Coat) colour paint wash (after cleaning/scraping/rubbing with sand paper / Brush, filling cracks with putty, applying 1 coat Exterior primer, etc.), along with garbage removal after paint (inclusive of tools, brush, ladder, bamboo frame to climb and other support materials for Indoor & outdoor works)</p>	<p>Provide Rate per Sq Mt (Cost including all materials & labour)</p> <p>i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost</p>
7.	<p>Synthetic Enamel paint on the Doors, Windows, MS Grill, Wall, GI corrugated Sheet shade (Assembly Stage Shade) Paint & Primer - ISI / BIS Marked - Paint Make / Brand - Asian Paint - Apcolite Premium Enamel Gloss / Berger Paints - Luxol HiGloss Enamel / Dulux - Super PU Satin Enamel Paint</p>	<p>Applying two coats of Synthetic Enamel paint in the Doors, Windows, MS Grill, Wall, GI corrugated Sheet shade (Assembly Stage Shade) etc (inclusive of tools, brush, ladder, bamboo frame to climb and other support materials for Indoor & outdoor works)</p>	<p>Provide Rate per Sq Mt (Cost including all materials & labour)</p> <p>i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost</p>

B] Electrical Work

S.N	Work	Technical Specification	Cost i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost
1.	Replacement of the Underground Cable of the Primary Building	25 Sq mm 1100V Aluminium Cable - ISI / BIS Marked Vidyalaya Meter Room to Primary Building Existing Main Switch under Stair Case about 280 Mt long	<p>Provide Rate per Mt (Cost including all materials & labour)</p> <p>i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost</p>
2.	Replacement of 100A 415V AC Main Switch (3 Phase)	100A 415V AC Main Switch (3 Phase) - ISI / BIS Marked Vidyalaya Meter Room near Maim Gate	<p>Provide Rate per Piece (Cost including all materials & labour)</p> <p>i)Materials Cost ii) Labour Cost iii) GST% iv)Total GST v)Total Cost</p>

3.	Replacement of 6A / 16A 240V AC One Way Switch (Single Phase)	ISI / BIS Marked i) 6A 240V AC One Way Switch (Single Phase) - ii) 16A 240V AC One Way Switch (Single Phase)	Provide Rate per Piece (Cost including all materials & labour) i) Materials Cost ii) Labour Cost iii) GST% iv) Total GST v) Total Cost
4.	Replacement of 6A / 16A 240V AC Wall Socket	i) 6A 240V AC - Wall Socket - ISI / BIS Marked ii) 16A 240V AC - Wall Socket - ISI / BIS Marked	Provide Rate per Piece (Cost including all materials & labour) i) Materials Cost ii) Labour Cost iii) GST% iv) Total GST v) Total Cost

Prepared By – Mr. S. Majumdar, TGT-WE --




Staff Quarters Maintenance Committee Members

1. Mr. Banti Behari, TGT-S.Sc
2. Ms. Komal Pal, TGT-Math
3. Mrs. Uday Kumar, PRT

Signature

- 

- 

Sd/-

Principal